




Alaska Housing Finance Corporation  
LIO Building  
Anchorage, Alaska

# Evaluation of Cost Estimate for Downtown Development

## REPORT

October 10, 2013



**Prepared By:** \_\_\_\_\_



*Bratslavsky*  
CONSULTING ENGINEERS INC

500 W. 27<sup>th</sup> Ave, Suite A  
Anchorage, AK 99504  
907-272-5264  
[www.bce-ak.com](http://www.bce-ak.com)  
[mail@bce-ak.com](mailto:mail@bce-ak.com)

October 10, 2013

BCE Project # 1112.13

DeWayne "Doc" Crouse  
Construction Director  
Alaska Housing Finance Corporation  
4300 Boniface Parkway  
PO Box 101020  
Anchorage, Alaska 99510-1020  
Phone: (907) 330-8130  
E-mail: dcrouse@ahfc.us

RE: Cost Estimating Review Services for Downtown Development at 716 W 4<sup>th</sup> Avenue,  
Anchorage, AK

Dear Doc,

Bratslavsky Consulting Engineers, Inc. (BCE) has reviewed a cost estimate prepared for the Downtown Development at 716 W 4<sup>th</sup> Avenue, Anchorage, AK, as provided by the Alaska Housing Finance Corporation (AHFC) on September 12, 2013, along with the preliminary design drawings and a narrative. As requested by AHFC, this was a brief review only (restricted primarily by the client's schedule and the limited amount of information available). Therefore, BCE's evaluation of the estimate is based primarily on the comparison of square footage costs and unit prices to those for similar projects.

As noted above, BCE's review of the cost estimate was restricted by the limitations of the design (conceptual only) for this project. BCE received a set of very preliminary architectural plans and a narrative; no structural, mechanical, or electrical drawings were provided.

### *Executive Summary*

The cursory review of the contractor's cost estimate for this Downtown Development performed by BCE indicates that the cost estimate in general complies with standard estimating practices, and the prices can be compared to those provided by RSMeans.

The construction cost estimate for 716 W 4<sup>th</sup> Avenue, Anchorage, Alaska, was reviewed by BCE and was found to be in general not unreasonable, even though some items may be on the high side. Due to the preliminary nature of the contractor's design and construction cost estimate, a precise validation cannot be made at this time.

Currently, the estimate has a number of contingencies and allowances that are difficult to verify, including but not limited to the following:

- A) Required demolition and hazardous materials abatement have been estimated high.

- B) Costs for the required construction equipment, including cranes, lifts, and other material handling equipment, appear very high. BCE questions the need for all of this equipment, some of which appears to be redundant.
- C) Transparent interior partitions have been included as an allowance only at a fairly high price.
- D) BCE estimators consider that some costs, such as design and engineering, also may have been included more than once. For example, the cost of design for the photovoltaic system, mechanical design, and electrical design, have been included separately, even though the total design cost has already been accounted for.

The BCE cost estimators believe that the customer would be in a better position to negotiate this price if the project design were at a more advanced (complete) stage.

### ***Specific Comments Regarding the Cost Estimate***

BCE has reviewed the specific cost items for unit price reasonability. Due to time restrictions, only items with a relatively higher percentage of the total cost have been reviewed. Below is the list of these items, along with the corresponding comments:

#### **1. TOTAL ESTIMATED CONSTRUCTION COST**

The total estimated construction costs by CRITERION [dated 08-27-2013] is \$29,751,107. Direct Cost for Divisions 1 thru 16: \$26,631,890. Design and Engineer fees are included in this cost.

This project is being built under a Design-Build contract agreement.

Markups: Profit and Home Office General Markup (8%): \$ 2,263,710. Contractor markups are reasonable (Ref: RSMeans).

Bid price: Direct Costs + Markups: \$28,895,600 (excluding fees and bond costs, but including design fees).

#### **SPECIFIC COST ITEMS:**

#### **2. FEES & PREMIUMS: \$625,673**

The following costs should require a further review (since limited design only is provided):

- ROAD CLOSURE & TRAFFIC PERMITS: \$100,000
- PERFORMANCE & PAYMENT BOND, IF REQUIRED: \$229,834

The bond equals 1% of the Bid Price + Fees. This is usually based on contractor's experience. The Owner will likely require a bond for the construction of this project.

However, the bond price for projects of this size built by a contractor with a good record of past performance typically are lower.

3. GENERAL REQUIREMENTS

The General Requirements, excluding Design and Engineering, is estimated at 9.4% of Direct Costs. This amount is slightly higher than what is typical for a job of this size, but may not be unreasonable. (Ref: RSMeans: 6% to 8%)

Project Design & Engineering = \$1,306,644, which is 35% of total General Requirements costs, and 5.2% of the Direct Construction Cost. This is typical for this size of project (Ref: RSMeans).

4. 01508 TEMPORARY HEAT: 8.0 Months @ \$19,322.17 per MO

*Comment:* Temporary heat may not be needed for full 8 months.

5. CRANES SERVICE, HOISTS, BOOM LIFTS, SCAFFOLDING.

Equipment rental was included in the estimate, but may not be needed for the full time of construction as indicated. Currently the estimate includes 12 Months of equipment rental. This amount is 25.5% of Total General Requirements (including design).

6. Recommend to CONFIRM SCOPE OF SELECTIVE BUILDING DEMOLITION.

DEMO is not specifically called out in the structural or architectural narrative, and should still be confirmed. BCE estimates that the following work will be included:

- Remove the Anchor Bar on the east side of the main building.
- Remove the east, west, south, and north concrete walls from the existing building.
- Remove the existing north elevator and stair core (along with the northern penthouse).
- Infill the east side addition with a new meeting and hearing space in the basement and first floors.
- New permanent shoring along the northern edge of the Anchor Bar along 4th Ave, and on the eastern side adjacent to the existing building ~18 feet deep.
- Gravity load resisting system in the existing building is adequate, but needs to be modified where the north core stairs and elevator are being removed.
- Construct six story elevator and a stair core on the north end including foundation, floor, roof, and exterior walls.
- The lateral-load resisting system in the existing building must be completely revised with buckling restrain brace frames (BRBF).
- Note: Removal of exterior walls is not specifically called out; therefore, the estimate is based on visual depiction of the future building provided.



- It should be noted that the demolition quantity estimate by BCE is significantly less.

7. 02221 DEMOLITION SUBCONTRACTOR - AK DEMO: \$2,017,277 - 7.58% of Direct Costs

This item seems high and requires further explanation of what is included or excluded:

- The extent of interior structural demolition should be confirmed; e.g. BCE assumed the floors will stay. There are other specific structural issues affecting demolition that should be investigated.
- BCE questions whether all demolition (e.g. mechanical, plumbing, structural, interiors, hazardous materials) is included in Alaska Demo's price? There are additional demolition line items included in the GC demolition. *The question is if the demolition costs have been doubled up.*
- One cannot tell at this time how much "contingency" does this item include.
- Were there other demolition subcontract quotations solicited from other local qualified companies?
- Will the General Contractor furnish all cranes, hoist and rigging? If so, are any of these costs "doubled-up" in the Alaska Demolition's subcontract quotation?
- How long is it expected to perform this demolition work? (Will it be done in the winter? Will temporary heat be required for mass demolition work? Temporary heat may already be included).
- Some additional costs for this work may be included (or "doubled-up") in several other line items in (Criterion's) cost estimate, e.g. Material Handling, Hauling, Dump Fees. One would need to identify and discuss them.

8. 02220 ADDITIONAL ASBESTOS ABATEMENT - ALLOWANCE: \$300,000

This item requires explanation of why it is not included in the demolition quote (by Alaska Demolition).

9. 02300 SITE & UTILITY SUBCONTRACTOR - BCX: \$362,622 - 1.36% of Direct Costs

It is not clear to BCE what is included in this subcontract? Site utilities and hook-ups, such as water, sanitary sewer, storm water, and site access? One would need to verify that this work is not also included ('doubled up') in other work.

10. 02455 H PILING & LAGGING (BASEMENT SHORING): \$571,933

Did Criterion receive a subcontractor quotation for this work (is this cost confirmed)? If not, the scope of work should be investigated and detailed further.

11. 00310 FORMWORK

Total cost of concrete work is \$1,380,201 for Division 3000, which does not seem unreasonable. BCE'S estimate of quantities, however, provides a much lower number than in the contractor's estimate. There is not enough design detail at this time for BCE to confirm the actual quantity or the cost of concrete work.

#### 12. DIVISION 05000 METALS

The total for this division is \$2,211,554, or 8.3% of Direct Costs. Cost of fabricated steel is \$1.5 per pound. This is somewhat high.

Buckling Restraint Braces were counted as 104 ea. Is this a specialty item or just structural fabricated steel? The quantity of this material is consistent with BCE's estimate.

Estimated is 21,800 LF for cold-formed metal framing. Due to the lack of detailed design, BCE could not verify if this framing is not in the areas where the Kawneer exterior glazing or interior translucent glazing is already estimated. The total price as a percentage of the project is not unreasonable, but it would be good to confirm this material take-off and the price.

#### 13. DIVISION 06000: WOOD & PLASTIC

Costs for these materials and installation at 1.32% of Direct Costs appear okay.

It is provided as a "Budget Allowance for Custom Case work". This could possibly be a fairly low estimate for cabinetry and case work, and should be verified by the Owner/ User.

#### 14. DIVISION 07000 THERMAL & MOISTURE

Metal Siding Panels. It was not clear as to where will these be installed. Are these the Mechanical Penthouse walls? At \$552,824, or \$36.61 per square foot, they seem to be quite expensive.

Membrane roof price is not unreasonable.

Roofing price seems to be in line with the industry standard for insulated, contoured for drainage EPDM roofing prices and should also include all flashing.

#### 15. DIVISION 08900: DOORS & WINDOWS

Interior door and frame prices are reasonable assuming they include all door hardware, too. This cost number comes in at \$2,264.00 per 'opening'. BCE believes that this is a good price for high quality door frames and hardware installed. While this reviewer had no design information on the grade of hardware, at this price the supplied materials should be of good quality and by a reputable manufacturer (i.e., Von Duprin, Schlage, Best, Precision, LCN).

#### 16. 08900 GLAZED CURTAIN WALL & ALUMINUM ENTRANCES

The total price of \$2,103,322 is 7.90% of Direct Costs.

The system quoted in the design narrative is a Kawneer product and should be at least a 6" back member extrusion depending on the structural/ wind load design requirements. The price is around \$85.00 per square foot. This should be a good number, especially if utilizing the Kawneer Versoliel Sun Shade extrusion (as noted).

#### 17. DIVISION 09100: FINISHES

Partition Studs, GWB and Ceiling costs appear reasonable.

Painting and Taping is estimated at \$452,627, or \$1.7% of Direct Costs. Tape and paint price seems perfectly reasonable based on the square footage of sheetrock; it comes out to about \$1.36 per square foot, adding in the suspended ceilings. Painted and taped wall surface should be verified though with regard to the other materials listed (e.g. translucent partitions, etc.)

Flooring: This is another allowance price (\$6.83/SF), and should be negotiated based on quality of flooring used. It should be noted that this price does not reflect floor prep work. This price also seems reasonable for good commercial quality ceramic tile, carpets, etc.

Ceilings: This number calculates out to \$5.20 per SF, and is a good number for non regular, non fire rated suspended ceilings. This would be a standard grid and tile (I.E. Armstrong Cortega).

#### 18. DIVISION 100000: SPECIALTIES

All prices for the items included in the estimate appear reasonable.

Is there a contract requirement for **1% for [Modular] Art?**

It is currently **excluded** from the Criterion's estimate.

#### 19. 14000: GLASS WALL SYSTEMS

ALLOWANCE of \$654,983 (or 2.46% Project Direct Costs) has been included in the project budget estimate.

From the architectural narrative this system will be used for the Office Suites.

- Translucent and Clear Glass Partitions between Inner and Outer Offices.
- Translucent and Clear Glass Partitions between Office Suites and Common Corridor.

Floor - carpet or similar; ceiling - combination of GWB and 2'X2' ACT.

Almost all walls at exterior walls in the offices will be designed with full glazing. It appears that this allowance is for most of the interior office walls to get glass as well (Translucent Glazing is noted). This may be done to get light into the building, but still allow for relative

privacy in the offices. The current base price for the translucent partitions (per our check) is about \$74.00 per square foot, which is very high. *However, because the price is given as an allowance, BCE staff would think it is up for negotiations.*

Notes:

It is not clear whether Criterion estimated the quantity of the total area of glass partitions required. Did they get a material supplier and/or an installing subcontractor quotation? The quantity may be "doubled-up" with GWB partition framing (see above).

## 20. DIVISION 14200 - ELEVATORS

Elevator costs are reasonable. Could be confirmed by the quote from the supplier (i.e. Otis Elevator).

## 21. DIVISION 15000, MECHANICAL

The MECHANICAL work will be accomplished under a separate Design-Build Contract. The total cost of this work is \$4,119,269, which is \$63.37 per square foot, or 15.47% of the total project Direct Cost. BCE believes that as a budgetary estimate this number is on the "conservative" / high side (Ref: RSMeans). This estimate is about 10-15 percent higher than what one would expect for this type of building (even with LEED / energy efficient features).

There are EXCLUSIONS in the mechanical estimate section:

- Mechanical Demolition is excluded (assumed to be performed by Alaska Demolition);
- Demolition of all plumbing systems, plumbing fixtures, HVAC systems;
- Work excludes all utility connections.

Work INCLUDED in the mechanical estimate.

The contractor's cost estimate currently includes the following items (as identified in the design narrative and other supplementary documentation provided for BCE review):

- Mechanical design and engineering.
- LEED Design Criteria.
- Fire Protection:
  - Subcontract price for a wet-pipe sprinkler system is included in the estimate, which is reasonable; however, a new fire pump may be needed (which is excluded from this estimate).
  - New fire department connection and sprinkler riser are included
- Plumbing
  - 6" Water Service; Sanitary Sewer Service; Gas Meter Connections (See BCX Utility Contractor quote above)
  - Natural gas piping

- New duplex lift station needed. Sump pumps
- Water pump package
- Copper, CPVC, PEX piping
- Two water heaters
- All new plumbing fixtures and floor drains
- New rain leader piping
- HVAC
  - 2 high efficiency boilers, controls, mechanical room piping;
  - Fin-tube radiation all along building perimeter at floors;
  - Cabinet unit heaters in entrances;
  - Roof top packaged HVAC unit. Building ventilation system variable air volume with sound control.
  - Terminal Heating Equipment: VAV boxes for terminal air supply w/Coils, etc.
  - IT Room Cooling refrigerator systems (2 ea).
  - Snowmelt in 3 areas: Front sidewalk, South rear entry/loading, and parking ramp will use a separate boiler.
- DDC Controls
  - Trane equipment interfaces. Pricing falls within the industry standards. VTC also is in a good range. The customer should find out if either of these includes *warranty and upgrades*, as there are high yearly costs for these items that are often overlooked.

## 22. DIVISION 16000, ELECTRICAL

The ELECTRICAL work will be accomplished under a separate Design-Build Contract. The total cost of \$3,054,429 for the electrical is \$46.99 per square foot, which is 11.47% of the Direct Cost. This is not unreasonable as this is believed to be a high budgetary estimate (Ref: RSMeans); it is "conservative" / high side. This item also includes \$319,000 for electrical engineering. This appears to be in addition to the total project design costs, which may be a duplication of costs.

Work INCLUDED in the electrical estimate.

The contractor's cost estimate currently includes the following items (as identified in the design narrative and other supplementary documentation provided to BCE):

- A main distribution switchboards consisting of metering equipment and overcurrent protection for distribution and branch circuit panels.
- Feeders to distribution and branch circuit panels.
- Branch circuit panels for power, lighting, HVAC, etc.
- Branch circuit wiring systems for equipment, lighting, duplex receptacles, appliances, motors, motor starters, etc., as required.
- Wall switches, duplex receptacles and other wiring devices.

- All hangers, anchors, sleeves, chases, support for fixture, and electrical materials and equipment.
- Interior lighting fixtures, controls complete with all lamps.
- Wiring and connections to all equipment furnished by the owner.
- Exterior lighting and controls.
- Telecommunication system.
- Fire Alarm system with monitoring of sprinkler system.
- Door Access.
- CCTV System.
- Cable TV system.
- 150 KW Standby Power Generator

### ***Conclusions and Recommendations***

This construction cost estimate for the Downtown Development at 716 W 4<sup>th</sup> Avenue, Anchorage, Alaska, was found to be not unreasonable in general, even though some items may be on the high side. There are several Allowances that will need to be verified (confirmed) in the future as the design is being completed.

Because this is a design-build project, it is prudent for the customer to make sure that the materials used in the building comply with the user's requirements and specifications. The project budget can definitely support very good to excellent quality of materials and installation workmanship.

It is also advisable to verify such items as warranties and upgrades that will come in the future during the building use.

Please do not hesitate to contact us with any questions or requests for additional information regarding this report.

Sincerely,



Tanya Bratslavsky, P.E., S.E., AVS  
President

#### Attachments:

Appendix A - LIO Building Construction Estimate by Criterion General, LLC  
Appendix B - LIO Building Construction Estimate Worksheet by BCE  
Appendix C - Photographs by BCE



# **Appendix A**

LIO 4th Ave Budget 8-27-13.xls

[illegible]



| DIVISION 01000, GENERAL REQUIREMENTS |                                           |                 |       |       |       |            |       |           |       |             |            |                |
|--------------------------------------|-------------------------------------------|-----------------|-------|-------|-------|------------|-------|-----------|-------|-------------|------------|----------------|
| CODE                                 | DESCRIPTION                               | COMPOSITE RATE: |       | LABOR |       | MATERIAL   |       | EQUIP/MNT |       | SUB / OTHER |            | TOTALS         |
|                                      |                                           | QUAN.           | /HR   | UNIT  | HRS   | TOTAL      | UNIT  | TOTAL     | UNIT  | TOTAL       | UNIT       |                |
| JOB DURATION                         |                                           | 13 mo           |       |       |       |            |       |           |       |             |            |                |
| JOB ADMINISTRATION                   |                                           |                 |       |       |       |            |       |           |       |             |            |                |
| 01300                                | Project design & engineering              | 1.0             | job   | 80    | 80    | 6644.33    | 0     | 0.00      | 0     | 0.00        | 1300000.00 | \$1,306,644.33 |
| 01310                                | Exploratory & asbuilt work                | 1.0             | job   | 0     | 0     | 0.00       | 0     | 0.00      | 0     | 0.00        | 22000.00   |                |
| 01310                                | Project manager                           | 13.0            | mo    | 60    | 780   | 64782.23   | 400   | 5200.00   | 0     | 0.00        | 0.00       |                |
| 01320                                | Project supervision                       | 55.3            | wks   | 50    | 2763  | 229437.08  | 0     | 0.00      | 0     | 0.00        | 0.00       |                |
| 01325                                | Safety program manager                    | 13.0            | mo    | 32    | 416   | 34550.52   | 0     | 0.00      | 0     | 0.00        | 0.00       |                |
| 01330                                | Project engineer / submittals / O&M's     | 13.0            | mo    | 20    | 260   | 21594.08   | 500   | 6500.00   | 0     | 0.00        | 0.00       | \$28,094.08    |
| 01340                                | Project coordinator                       | 13.0            | mo    | 10    | 130   | 10797.04   | 0     | 0.00      | 0     | 0.00        | 0.00       |                |
| 01350                                | Expediting / purchasing                   | 13.0            | mo    | 40    | 520   | 43188.16   | 0     | 0.00      | 0     | 0.00        | 0.00       |                |
| Q.C. / FIELD ENGR.                   |                                           |                 |       |       |       |            |       |           |       |             |            |                |
| 01400                                | Construction staking & as-built plot plan | 1.0             | job   | 0     | 0     | 0.00       | 0     | 0.00      | 0     | 0.00        | 8000.00    | \$8,000.00     |
| 01430                                | Testing & special inspections             | 1.0             | job   | 0     | 0     | 0.00       | 0     | 0.00      | 0     | 0.00        | 80000.00   |                |
| TEMPORARY FACILITIES                 |                                           |                 |       |       |       |            |       |           |       |             |            |                |
| 01501                                | Field office                              | 13.0            | mo    | 8     | 104   | 8637.63    | 0     | 0.00      | 2000  | 26000.00    | 0          | 0.00           |
| 01501                                | Temp crew parking - Use garage            | 0.0             | mo    | 0     | 0     | 0.00       | 0     | 0.00      | 0     | 0.00        | 0.00       |                |
| 01502                                | Project signs                             | 1.0             | ea    | 10    | 10    | 830.54     | 1000  | 1000.00   | 0     | 0.00        | 0.00       | 0.00           |
| 01503                                | Storage Containers                        | 2.0             | ea    | 0     | 0     | 0.00       | 0     | 0.00      | 1500  | 3000.00     | 0          |                |
| 01503                                | Storage area / security fence             | 600.0           | lf    | 0.05  | 30    | 2491.62    | 0     | 0.00      | 8     | 4800.00     | 0          | 0.00           |
| 01504                                | Temporary toilets                         | 13.0            | mo    | 0     | 0     | 0.00       | 0     | 0.00      | 0     | 0.00        | 1050       |                |
| 01505                                | Temp electric service                     | 1.0             | job   | 100   | 100   | 8305.41    | 0     | 0.00      | 0     | 0.00        | 13650.00   | \$13,650.00    |
| 01506                                | Electricity                               | 13.0            | mo    | 0     | 0     | 0.00       | 0     | 0.00      | 0     | 0.00        | 20000.00   |                |
| 01507                                | Temporary lights                          | 13.0            | flrs  | 10    | 130   | 10797.04   | 1000  | 13000.00  | 0     | 0.00        | 0.00       | 0.00           |
| 01508                                | Temporary heat                            | 8.0             | mo    | 40    | 320   | 26577.33   | 15000 | 120000.00 | 1000  | 8000.00     | 0          |                |
| 01509                                | Telephones                                | 13.0            | mo    | 0     | 0     | 0.00       | 0     | 0.00      | 100   | 1300.00     | 250        | 3250.00        |
| 01510                                | Temp weather protection                   | 6.0             | flrs  | 125   | 750   | 62290.61   | 4000  | 24000.00  | 0     | 0.00        | 0          |                |
| 01510                                | Temp pedestrian walkways                  | 1.0             | job   | 100   | 100   | 8305.41    | 4000  | 4000.00   | 0     | 0.00        | 0          | 0.00           |
| 01511                                | Snow removal                              | 5.0             | mo    | 40    | 200   | 16610.83   | 0     | 0.00      | 0     | 0.00        | 0          |                |
| 01512                                | Cleanup periodic                          | 13.0            | mo    | 140   | 1820  | 151158.54  | 0     | 0.00      | 0     | 0.00        | 0          | 0.00           |
| 01513                                | Cleanup final, Inc. windows               | 1.0             | job   | 200   | 200   | 16610.83   | 200   | 200.00    | 0     | 0.00        | 8000       |                |
| 01514                                | Safety supplies                           | 1.0             | job   | 0     | 0     | 0.00       | 8000  | 8000.00   | 0     | 0.00        | 0          | 0.00           |
| 01515                                | Material handling                         | 13.0            | mo    | 200   | 2600  | 215940.78  | 0     | 0.00      | 0     | 0.00        | 0          |                |
| 01516                                | Trash haul, dumpsters                     | 13.0            | mo    | 24    | 312   | 25912.89   | 0     | 0.00      | 600   | 7800.00     | 1200       | \$49,312.89    |
| EQUIPMENT                            |                                           |                 |       |       |       |            |       |           |       |             |            |                |
| 01600                                | Consumables                               | 1.0             | job   | 0     | 0     | 0.00       | 18000 | 18000.00  | 0     | 0.00        | 0          | 0.00           |
| 01620                                | Scaffolding / man lifts                   | 12.0            | mo    | 0     | 0     | 0.00       | 0     | 0.00      | 3500  | 42000.00    | 0          |                |
| 01630                                | Job trucks (pickup, flatbed)              | 13.0            | mo    | 0     | 0     | 0.00       | 0     | 0.00      | 1200  | 15600.00    | 0          | 0.00           |
| 01640                                | Bob Truck                                 | 8.0             | mo    | 0     | 0     | 0.00       | 0     | 0.00      | 3000  | 24000.00    | 0          |                |
| 01640                                | Forklift                                  | 10.0            | mo    | 0     | 0     | 0.00       | 0     | 0.00      | 3000  | 30000.00    | 0          | 0.00           |
| 01640                                | Aerial Boom Lift                          | 12.0            | mo    | 0     | 0     | 0.00       | 0     | 0.00      | 8000  | 96000.00    | 0          |                |
| 01650                                | Misc. rental                              | 13.0            | mo    | 0     | 0     | 0.00       | 0     | 0.00      | 500   | 6500.00     | 0          | 0.00           |
| 01660                                | Fuel & maintenance                        | 13.0            | mo    | 30    | 390   | 32391.12   | 800   | 10400.00  | 0     | 0.00        | 0          |                |
| 01670                                | Crane Service                             | 11.0            | mo    | 200   | 2200  | 182719.12  | 3200  | 35200.00  | 30000 | 330000.00   | 0.00       | \$547,919.12   |
| 01680                                | Man / equipment hoist                     | 7.0             | mo    | 160   | 1120  | 93020.64   | 0     | 0.00      | 9000  | 63000.00    | 6500       |                |
| FREIGHT                              |                                           |                 |       |       |       |            |       |           |       |             |            |                |
| 01800                                | General ocean freight-sea to jobsite      | 4.0             | loads | 0     | 0     | 0.00       | 0     | 0.00      | 0     | 0.00        | 26000.00   | \$26,000.00    |
| 01860                                | Mobe / demobe                             | 1.0             | job   | 80    | 80    | 6644.33    | 2000  | 2000.00   | 0     | 0.00        | 0.00       |                |
| GENERAL REQUIREMENTS, TOTAL          |                                           |                 |       |       | 15415 | 1280238.12 |       | 247500.00 |       | 658000.0    | 1581000.00 | \$3,766,738.12 |



| DIVISION 02000, SITEWORK |                                            |                 |               |             |        |         |     |           |           |             |         |            |                |
|--------------------------|--------------------------------------------|-----------------|---------------|-------------|--------|---------|-----|-----------|-----------|-------------|---------|------------|----------------|
| CODE                     | DESCRIPTION                                | COMPOSITE RATE: | \$83.05 /HR   | QUAN.       | UNIT   | LABOR   |     | MATERIAL  | EQUIP/MNT | SUB / OTHER |         | TOTALS     |                |
|                          |                                            |                 |               |             |        | UNIT    | HRS |           |           | UNIT        | TOTAL   |            |                |
| 02220                    | Additional Asbestos Abatement - ALLOWMAN   |                 | 1.0 job       |             | 0      | 0       |     | 0         | 0.00      | 0           | 0.00    | 300000.00  | \$300,000.00   |
| 02221                    | Demolition subcontractor - AK DEMO         |                 | 1.0 job       |             | 500    | 500     |     | 0         | 0.00      | 1976200     | 0.00    | 1976200.00 | \$2,017,727.07 |
| 02221                    | Temporary shoring - building               |                 | 1.0 job       |             | 400    | 400     |     | 20000     | 20000.00  | 0           | 0.00    | 0          | 0.00           |
| 02221                    | Temporary shoring - garage                 |                 | 1.0 job       |             | 500    | 500     |     | 20000     | 20000.00  | 0           | 0.00    | 0          | 0.00           |
| 02221                    | Additional demolition                      |                 | 6.0 flrs      |             | 100    | 600     |     | 0         | 0.00      | 500         | 3000.00 | 0          | 0.00           |
| 02221                    | Haul off misc demo debris                  |                 | 20.0 lds      |             | 4      | 80      |     | 0         | 0.00      | 350         | 7000.00 | 650        | 13000.00       |
| 02221                    | Remove floor adhesives                     |                 | 61000.0 sf    |             | 0.0075 | 458     |     | 0         | 0.00      | 0.05        | 3050.00 | 0          | 0.00           |
| 02300                    | Traffic control plan                       |                 | 1.0 job       |             | 100    | 100     |     | 20000     | 20000.00  | 0           | 0.00    | 8000       | 8000.00        |
| 02300                    | Traffic control plan - flagger             |                 | 8.0 mo        |             | 160    | 1280    |     | 0         | 0.00      | 0           | 0.00    | 0          | 0.00           |
| 02300                    | Site & utility subcontractor - BCX         |                 | 1.0 job       |             | 40     | 40      |     | 0         | 0.00      | 0           | 0.00    | 359300     | 359300.00      |
| 02316                    | Trenching for M & E-interior bldg          |                 | 500.0 lf      |             | 0.05   | 25      |     | 1         | 500.00    | 2.5         | 1250.00 | 0          | 0.00           |
| 02370                    | SWPPP management / street sweeping         |                 | 7.0 mo        |             | 60     | 420     |     | 500       | 3500.00   | 1000        | 7000.00 | 0          | 0.00           |
| 02455                    | H piling & lagging (basement shoring)      |                 | 120.0 lf      |             | 2      | 240     |     | 100       | 12000.00  | 0           | 0.00    | 4500       | 540000.00      |
| 02740                    | Asphalt pavement @ Alley                   |                 | 4000.0 sf     |             | 0      | 0       |     | 0         | 0.00      | 0           | 0.00    | 5          | 20000.00       |
| 02740                    | Asphalt pavement @ roads                   |                 | 4000.0 sf     |             | 0      | 0       |     | 0         | 0.00      | 0           | 0.00    | 5          | 20000.00       |
| 02740                    | Asphalt seal coat parking garage           |                 | 40300.0 sf    |             | 0      | 0       |     | 0         | 0.00      | 0           | 0.00    | 0.5        | 20150.00       |
| 02760                    | Paint markings - garage                    |                 | 120.0 ea      |             | 0      | 0       |     | 0         | 0.00      | 0           | 0.00    | 35         | 4200.00        |
| 02770                    | Curb & gutter patches                      |                 | 120.0 lf      |             | 0      | 0       |     | 0         | 0.00      | 0           | 0.00    | 40         | 4800.00        |
| 02775                    | Sidewalks & pads                           |                 | 3800.0 sf     |             | 0.025  | 95      |     | 5         | 19000.00  | 0           | 0.00    | 2          | 7600.00        |
| 02775                    | Ramp - garage                              |                 | 4000.0 sf     |             | 0.025  | 100     |     | 6         | 24000.00  | 0           | 0.00    | 3          | 12000.00       |
| 02820                    | Fences & gates-dumpster enclosure          |                 | 36.0 lf       |             | 1      | 36      |     | 120       | 4320.00   | 0           | 0.00    | 0          | 0.00           |
| 02820                    | Gates @ garage ramp                        |                 | 1.0 job       |             | 40     | 40      |     | 0         | 0.00      | 0           | 0.00    | 25000      | 25000.00       |
| 02900                    | Landscape planting                         |                 | 1.0 job       |             | 0      | 0       |     | 0         | 0.00      | 0           | 0.00    | 5000       | 5000.00        |
| 02900                    | Landscape furnishings (bike rack, benches) |                 | 8.0 ea        |             | 2      | 16      |     | 1000      | 8000.00   | 0           | 0.00    | 0          | 0.00           |
|                          |                                            |                 | 0.0           |             | 0      | 0       |     | 0         | 0.00      | 0           | 0.00    | 0          | 0.00           |
| DIVISION 02 , TOTAL      |                                            |                 |               |             |        | 4930    |     | 131320.00 |           | 21300.00    |         | 3315250.00 | \$3,877,285.41 |
| DIVISION 03000, CONCRETE |                                            |                 |               |             |        |         |     |           |           |             |         |            |                |
| CODE                     | DESCRIPTION                                | COMPOSITE RATE: | \$83.05 / HR  | QUAN.       | UNIT   | LABOR   |     | MATERIAL  | EQUIP/MNT | SUB / OTHER |         | TOTALS     |                |
|                          |                                            |                 |               |             |        | UNIT    | HRS |           |           | UNIT        | TOTAL   |            |                |
| 03100                    | Formwork                                   |                 | 23000.0 sf/sa |             | 0.1    | 2300    |     | 5         | 115000.00 | 0           | 0.00    | 0          | 0.00           |
| 03200                    | Reinforcing-purchase                       |                 | 190000 lb     |             | 0      | 0       |     | 0.75      | 142500.00 | 0           | 0.00    | 0          | 0.00           |
| 03200                    | Reinforcing place rebar                    |                 | 100.0 ton     |             | 0      | 0       |     | 0         | 0.00      | 0           | 0.00    | 900        | 90000.00       |
| 03200                    | Reinforcing place WWF                      |                 | 24572 sf      |             | 0.0025 | 61      |     | 0.4       | 9828.80   | 0           | 0.00    | 0          | 0.00           |
| 03300                    | Place footing, walls, grade beams          |                 | 582.0 cy      |             | 0.75   | 436.50  |     | 125       | 72750.00  | 15          | 8730.00 | 0          | 0.00           |
| 03300                    | Place concrete ballast SOG                 |                 | 580.0 cy      |             | 0.75   | 436.50  |     | 125       | 72500.00  | 15          | 8700.00 | 0          | 0.00           |
| 03300                    | Place concrete on grade/decks/infills      |                 | 362.0 cy      |             | 1      | 362.00  |     | 125       | 45250.00  | 25          | 9050.00 | 0          | 0.00           |
| 03300                    | Place & finish stairs & landings           |                 | 30.0 cy       |             | 3      | 90.00   |     | 125       | 3750.00   | 15          | 450.00  | 400        | 12000.00       |
| 03300                    | Place housekeeping pads                    |                 | 30.0 cy       |             | 3      | 90.00   |     | 125       | 3750.00   | 15          | 450.00  | 0          | 0.00           |
| 03300                    | Edge of deck infill                        |                 | 3000.0 sf     |             | 0.1    | 300.00  |     | 3         | 9000.00   | 1           | 3000.00 | 0          | 0.00           |
| 03300                    | Place misc. conc                           |                 | 50.0 cy       |             | 3      | 150.00  |     | 125       | 6250.00   | 0           | 0.00    | 0          | 0.00           |
| 03300                    | Garage - upgrades                          |                 | 1.0 job       |             | 2000   | 2000.00 |     | 30000     | 30000.00  | 0           | 0.00    | 0          | 0.00           |
| 03350                    | Finish concrete slabs                      |                 | 24572 sf      |             | 0      | 0       |     | 0         | 0.00      | 0           | 0.00    | 1.5        | 36858.00       |
| 03390                    | Curing / sealing                           |                 | 24572 sf      |             | 0.001  | 25      |     | 0.05      | 1228.60   | 0           | 0.00    | 0          | 0.00           |
| 03600                    | Grout column bases                         |                 | 20.0 ea       |             | 1      | 20      |     | 50        | 1000.00   | 0           | 0.00    | 0          | 0.00           |
| 03151                    | Sawcut control joints                      |                 | 1550.0 lf     |             | 0.035  | 54      |     | 0         | 0.00      | 0.5         | 775.00  | 0          | 0.00           |
| 03050                    | Epoxy Bolts                                |                 | 1.0 job       |             | 1500   | 1500    |     | 15000     | 15000.00  | 0           | 0.00    | 0          | 0.00           |
| 03050                    | Embedded items                             |                 | 1.0 job       |             | 200    | 200     |     | 8000      | 8000.00   | 0           | 0.00    | 0          | 0.00           |
| 03050                    | Anchor bolts & templates                   |                 | 120.0 ea      |             | 0.5    | 60      |     | 25        | 3000.00   | 0           | 0.00    | 0          | 0.00           |
| DIVISION 03 , TOTAL      |                                            |                 |               |             |        | 8084    |     | 538807.40 |           | 31155.00    |         | 138858.00  | \$1,380,209.51 |
|                          |                                            |                 |               | total yards | 4555.0 |         |     |           |           |             |         |            |                |



| DIVISION 04000, MASONRY          |                                   |        |           |       |           |           |               |            |                |
|----------------------------------|-----------------------------------|--------|-----------|-------|-----------|-----------|---------------|------------|----------------|
| COMPOSITE RATE:                  |                                   |        |           |       |           |           |               |            |                |
| CODE                             | DESCRIPTION                       | QUAN.  | / HR UNIT | UNIT  | LABOR HRS | TOTAL     | MATERIAL UNIT | TOTAL      | TOTALS         |
| 04200                            | Concrete masonry units            | 0.0    | blks      | 0     | 0         | 0.00      | 0             | 0.00       | \$0.00         |
| DIVISION 04, TOTAL               |                                   |        |           |       |           |           |               |            |                |
|                                  |                                   |        |           |       | 0         | 0.00      |               | 0.00       | \$0.00         |
| DIVISION 05000, METALS           |                                   |        |           |       |           |           |               |            |                |
| COMPOSITE RATE:                  |                                   |        |           |       |           |           |               |            |                |
| CODE                             | DESCRIPTION                       | QUAN.  | / HR UNIT | UNIT  | LABOR HRS | TOTAL     | MATERIAL UNIT | TOTAL      | TOTALS         |
| 05090                            | Welding rod, gas, bolts, supplies | 1.0    | job       | 0     | 0         | 0.00      | 2500          | 2500.00    | \$2,500.00     |
| 05100                            | Structural steel fabrication      | 440000 | lbs       | 0     | 0         | 0.00      | 1.5           | 660000.00  | \$660,000.00   |
| 05100                            | Buckling restraint braces         | 104    | ea        | 8     | 832       | 69101.05  | 2500          | 260000.00  | \$329,101.05   |
| 05100                            | Stairwells                        | 1      | ea        | 0     | 0         | 0.00      | 35000         | 35000.00   | \$35,000.00    |
| 05100                            | Structural steel erection         | 27572  | sf        | 0     | 0         | 0.00      | 0             | 0.00       | \$248,148.00   |
| 05100                            | Structural steel decking purchase | 27572  | sf        | 0     | 0         | 0.00      | 3             | 82716.00   | \$92,716.00    |
| 05100                            | Structural steel upgrades         | 1      | job       | 2200  | 2200      | 182719.12 | 100000        | 100000.00  | \$143,000.00   |
| 05100                            | Ship structural steel             | 22     | lds       | 0     | 0         | 0.00      | 0             | 0.00       | \$33,600.00    |
| 05200                            | Steel roof joists                 | 5600   | sf        | 0     | 0         | 0.00      | 6             | 0.00       | \$39,000.00    |
| 05200                            | Ship roof joist & deck            | 5      | lds       | 0     | 0         | 0.00      | 0             | 0.00       | \$278,642.55   |
| 05400                            | Cold-formed metal framing         | 21800  | lf        | 0.125 | 2725      | 226322.55 | 2.4           | 52320.00   | \$8,034.48     |
| 05500                            | Welded rebar @ pour stop          | 700    | ea        | 0.25  | 175       | 14534.48  | 5             | 3500.00    | \$1,896.65     |
| 05500                            | Angles openings through deck      | 1      | job       | 60    | 60        | 4983.25   | 3500          | 3500.00    | \$8,483.25     |
| 05500                            | Angles at elevator pits           | 3      | ea        | 4     | 12        | 996.65    | 300           | 900.00     | \$1,896.65     |
| 05500                            | Miscellaneous fabricated metals   | 1      | job       | 50    | 50        | 4152.71   | 5000          | 5000.00    | \$9,152.71     |
| 05500                            | Handrails                         | 600    | lf        | 0.1   | 60        | 4983.25   | 30            | 18000.00   | \$22,983.25    |
| 05500                            | Temporary guard rails             | 2400   | lf        | 0.035 | 84        | 6976.55   | 4             | 9600.00    | \$16,576.55    |
| DIVISION 05, TOTAL               |                                   |        |           |       |           |           |               |            |                |
|                                  |                                   |        |           |       | 6198      | 514769.59 |               | 1266636.00 | \$2,211,553.59 |
| DIVISION 06000, WOOD AND PLASTIC |                                   |        |           |       |           |           |               |            |                |
| COMPOSITE RATE:                  |                                   |        |           |       |           |           |               |            |                |
| CODE                             | DESCRIPTION                       | QUAN.  | / HR UNIT | UNIT  | LABOR HRS | TOTAL     | MATERIAL UNIT | TOTAL      | TOTALS         |
| 06100                            | Curbs cants blocking              | 4000.0 | bf        | 0.04  | 160       | 13288.66  | 3             | 12000.00   | \$25,288.66    |
| 06160                            | Sheathing - data boards           | 280.0  | sf        | 0.025 | 7         | 581.38    | 1             | 280.00     | \$861.38       |
| 06160                            | Sheathing - parapets              | 1800.0 | bf        | 0.025 | 45        | 3737.44   | 1.2           | 2160.00    | \$5,897.44     |
| 06160                            | Sheathing                         | 1700.0 | sf        | 0.025 | 43        | 3529.80   | 1.4           | 2380.00    | \$5,909.80     |
| 06200                            | Modular art wall                  | 0.0    | ea        | 10    | 0         | 0.00      | 5000          | 0.00       | \$0.00         |
| 06200                            | Custom floor base                 | 3000.0 | lf        | 0.35  | 1050      | 87206.85  | 10            | 30000.00   | \$117,206.85   |
| 06410                            | Custom casework - security desk   | 1.0    | job       | 20    | 20        | 1661.08   | 20000         | 20000.00   | \$21,661.08    |
| 06410                            | Custom casework - allowance       | 1.0    | job       | 150   | 150       | 12458.12  | 125000        | 125000.00  | \$137,458.12   |
| 06415                            | Solid surface @ restrooms         | 128.0  | lf        | 0.45  | 58        | 4783.92   | 200           | 25600.00   | \$30,383.92    |
| 06600                            | FRP panels - janitor closets      | 900.0  | sf        | 0.045 | 41        | 3363.69   | 3.5           | 3150.00    | \$6,513.69     |
| DIVISION 06, TOTAL               |                                   |        |           |       |           |           |               |            |                |
|                                  |                                   |        |           |       | 1573      | 130610.95 |               | 220570.00  | \$351,180.95   |

| DIVISION 07000, THERMAL AND MOISTURE |                                          |         |      |        |      |          |           |          |           |             |            |                |
|--------------------------------------|------------------------------------------|---------|------|--------|------|----------|-----------|----------|-----------|-------------|------------|----------------|
| COMPOSITE RATE: \$83.05 / HR         |                                          |         |      |        |      |          |           |          |           |             |            |                |
| CODE                                 | DESCRIPTION                              | QUAN.   | UNIT | LABOR  |      | MATERIAL |           | EQUIPMNT |           | SUB / OTHER |            | TOTALS         |
|                                      |                                          |         |      | UNIT   | HRS  | UNIT     | TOTAL     | UNIT     | TOTAL     | UNIT        | TOTAL      |                |
| 07110                                | Foundation membrane - E/P                | 0.0     | SF   | 0      | 0    | 0        | 0.00      | 0        | 0.00      | 0           | 0.00       | \$0.00         |
| 07110                                | Damp proofing - E/P                      | 0.0     | SF   | 0      | 0    | 0        | 0.00      | 0        | 0.00      | 0           | 0.00       | \$0.00         |
| 07210                                | Foundation insulation - E/P              | 0.0     | SF   | 0      | 0    | 0        | 0.00      | 0        | 0.00      | 0           | 0.00       | \$0.00         |
| 07210                                | Garage ramp                              | 4000.0  | SF   | 0.0075 | 30   | 1.6      | 2491.62   | 0        | 6400.00   | 0           | 0.00       | \$8,891.62     |
| 07210                                | Sidewalk insulation                      | 2000.0  | SF   | 0.0075 | 15   | 1.6      | 1245.81   | 0        | 3200.00   | 0           | 0.00       | \$4,445.81     |
| 07210                                | Building insulation-core acoustical      | 38500.0 | SF   | 0      | 0    | 0        | 0.00      | 0        | 0.00      | 1.5         | 57750.00   | \$57,750.00    |
| 07260                                | Building insulation- exterior wall       | 32000.0 | SF   | 0      | 0    | 0        | 0.00      | 0        | 0.00      | 2           | 64000.00   | \$64,000.00    |
| 07260                                | Air barriers                             | 15100.0 | SF   | 0.0075 | 113  | 0.85     | 9405.88   | 0        | 12835.00  | 0           | 0.00       | \$22,240.88    |
| 07400                                | Covered utility soffit panels            | 1280.0  | SF   | 0.08   | 102  | 30       | 8504.74   | 0        | 38400.00  | 0           | 0.00       | \$46,904.74    |
| 07400                                | Metal siding panels                      | 15100.0 | SF   | 0.2    | 3020 | 20       | 250823.52 | 0        | 302000.00 | 0           | 0.00       | \$552,823.52   |
| 07400                                | Mechanical room panels                   | 3240.0  | SF   | 0.2    | 648  | 50       | 53819.09  | 0        | 162000.00 | 0           | 0.00       | \$215,819.09   |
| 07500                                | Membrane roofing ALLOWANCE - E/P         | 1.0     | job  | 0      | 0    | 0        | 0.00      | 0        | 0.00      | 375000      | 375000.00  | \$375,000.00   |
| 07600                                | Flashing & sheet metal trim              | 4000.0  | Lf   | 0.03   | 120  | 5        | 9966.50   | 0        | 20000.00  | 0           | 0.00       | \$29,966.50    |
| 07800                                | Fire stopping-safing @ penetrations      | 400.0   | ea   | 0.5    | 200  | 5        | 16610.83  | 0        | 2000.00   | 0           | 0.00       | \$18,610.83    |
| 07800                                | Fire stopping-perimeter angles           | 3690.0  | Lf   | 0.125  | 461  | 6        | 38308.72  | 0        | 22140.00  | 0           | 0.00       | \$60,448.72    |
| 07800                                | Spray fireproofing - Bradshaw            | 68848.0 | SF   | 0      | 0    | 0        | 0.00      | 0        | 0.00      | 2.75        | 189332.00  | \$189,332.00   |
| 07900                                | Caulking & sealants - interiors          | 1.0     | job  | 40     | 40   | 400      | 3322.17   | 0        | 400.00    | 0           | 0.00       | \$3,722.17     |
| 07900                                | Caulking & sealants - exteriors          | 1.0     | job  | 80     | 80   | 800      | 6644.33   | 0        | 800.00    | 0           | 0.00       | \$7,444.33     |
| DIVISION 07, TOTAL                   |                                          |         |      |        | 4830 |          | 401143.22 |          | 570175.00 |             | 686082.00  | \$1,657,400.22 |
| DIVISION 08000, DOORS AND WINDOWS    |                                          |         |      |        |      |          |           |          |           |             |            |                |
| COMPOSITE RATE: \$83.05 / HR         |                                          |         |      |        |      |          |           |          |           |             |            |                |
| CODE                                 | DESCRIPTION                              | QUAN.   | UNIT | LABOR  |      | MATERIAL |           | EQUIPMNT |           | SUB / OTHER |            | TOTALS         |
|                                      |                                          |         |      | UNIT   | HRS  | UNIT     | TOTAL     | UNIT     | TOTAL     | UNIT        | TOTAL      |                |
| 08100                                | HM frames & doors                        | 95.0    | ea   | 8      | 760  | 1600     | 63121.15  | 0        | 0.00      | 0           | 0.00       | \$215,121.15   |
| 08310                                | Access doors                             | 20.0    | ea   | 1      | 20   | 35       | 1661.08   | 0        | 0.00      | 0           | 0.00       | \$2,361.08     |
| 08400                                | Forms and surface glass ALLOWANCE        | 1500.0  | SF   | 0.1    | 150  | 75       | 12458.12  | 0        | 0.00      | 0           | 0.00       | \$124,958.12   |
| 08800                                | Glass & Glazing                          | 1.0     | job  | 32     | 32   | 4000     | 2657.73   | 0        | 0.00      | 0           | 0.00       | \$6,657.73     |
| 08900                                | Extruded aluminum sills                  | 0.0     | Lf   | 0.025  | 0    | 8        | 0.00      | 0        | 0.00      | 0           | 0.00       | \$0.00         |
| 08900                                | Canopies                                 | 1.0     | job  | 10     | 10   | 0        | 830.54    | 0        | 0.00      | 15000       | 15000.00   | \$15,830.54    |
| 08900                                | Glazed curtain wall & aluminum entrances | 1.0     | job  | 40     | 40   | 0        | 3322.17   | 0        | 0.00      | 2100000     | 2100000.00 | \$2,103,322.17 |
| DIVISION 08, TOTAL                   |                                          |         |      |        | 1012 |          | 84050.79  |          | 269200.00 |             | 2115000.00 | \$2,468,250.79 |



| DIVISION 09000. FINISHES    |                                     | COMPOSITE RATE: | \$83.05 / HR | QUAN. | UNIT | LABOR  |       | TOTAL     | MATERIAL |           | EQUIPMNT |         | SUB / OTHER |            | TOTALS         |
|-----------------------------|-------------------------------------|-----------------|--------------|-------|------|--------|-------|-----------|----------|-----------|----------|---------|-------------|------------|----------------|
| CODE                        | DESCRIPTION                         |                 |              |       |      | UNIT   | HRS   |           | UNIT     | TOTAL     | UNIT     | TOTAL   | UNIT        | TOTAL      |                |
| 09100                       | Metal studs- furring interior       | 51486 lf        |              |       |      | 0.035  | 1802  | 149664.40 | 0.75     | 38614.50  | 0        | 0.00    | 0           | 0.00       | \$188,278.90   |
| 09100                       | Metal studs- partition interior     | 111119 lf       |              |       |      | 0.035  | 3889  | 323011.27 | 1.1      | 122230.90 | 0        | 0.00    | 0           | 0.00       | \$445,242.17   |
| 09120                       | Gyp ceiling suspension systems      | 18298.0 sf      |              |       |      | 0.05   | 915   | 75986.24  | 3        | 54894.00  | 0        | 0.00    | 0           | 0.00       | \$130,880.24   |
| 09260                       | GWB- stock & hang                   | 298830 sf       |              |       |      | 0.01   | 2988  | 248190.70 | 0.5      | 149415.00 | 0        | 0.00    | 0           | 0.00       | \$397,605.70   |
| 09280                       | Exterior Gyp                        | 15100 sf        |              |       |      | 0.02   | 302   | 25082.35  | 0.65     | 9815.00   | 0        | 0.00    | 0           | 0.00       | \$34,897.35    |
| 09260                       | Shaft wall                          | 14000.0 sf      |              |       |      | 0.04   | 560   | 46510.32  | 4        | 56000.00  | 0        | 0.00    | 0           | 0.00       | \$102,510.32   |
| 09260                       | Tile backer                         | 2224.0 sf       |              |       |      | 0.025  | 56    | 4617.81   | 1.15     | 2557.60   | 0        | 0.00    | 0           | 0.00       | \$7,175.41     |
| 09300                       | Tile - ALLOWANCE                    | 1.0 job         |              |       |      | 20     | 20    | 1661.08   | 0        | 0.00      | 0        | 0.00    | 200000      | 200000.00  | \$201,661.08   |
| 09510                       | Ceilings ALLOWANCE                  | 50000.0 sf      |              |       |      | 0.0025 | 125   | 10381.77  | 0        | 0.00      | 0        | 0.00    | 5           | 250000.00  | \$260,381.77   |
| 09610                       | Floor prep                          | 60000.0 sf      |              |       |      | 0.01   | 600   | 49832.49  | 0.05     | 3000.00   | 0        | 0.00    | 0           | 0.00       | \$52,832.49    |
| 09680                       | Flooring - ALLOWANCE                | 60000.0 sf      |              |       |      | 0.001  | 60    | 4983.25   | 0        | 0.00      | 0        | 0.00    | 6.75        | 405000.00  | \$409,983.25   |
| 09680                       | Entry floor system                  | 1.0 job         |              |       |      | 40     | 40    | 3322.17   | 15000    | 15000.00  | 0        | 0.00    | 0           | 0.00       | \$18,322.17    |
| 09900                       | Painting & taping                   | 1.0 job         |              |       |      | 50     | 50    | 4152.71   | 0        | 0.00      | 0        | 0.00    | 448474      | 448474.00  | \$452,626.71   |
| 09900                       | Painting - garage                   | 1.0 job         |              |       |      | 20     | 20    | 1661.08   | 0        | 0.00      | 0        | 0.00    | 65068       | 65068.00   | \$86,729.08    |
| 09950                       | Wallcoverings - restroom ALLOWANCE  | 10780.0 sf      |              |       |      | 0      | 0     | 0.00      | 0        | 0.00      | 0        | 0.00    | 8           | 86240.00   | \$86,240.00    |
| 09950                       | Wallcoverings fancy- ALLOWANCE      | 770.0 sf        |              |       |      | 0      | 0     | 0.00      | 0        | 0.00      | 0        | 0.00    | 75          | 57750.00   | \$57,750.00    |
| DIVISION 09. TOTAL          |                                     |                 |              |       |      |        | 11427 | 949057.64 |          | 451527.00 |          | 0.00    |             | 1512532.00 | \$2,913,116.64 |
| DIVISION 10000. SPECIALTIES |                                     |                 |              |       |      |        |       |           |          |           |          |         |             |            |                |
| CODE                        | DESCRIPTION                         | COMPOSITE RATE: | \$83.05 / HR | QUAN. | UNIT | UNIT   | HRS   | TOTAL     | UNIT     | TOTAL     | UNIT     | TOTAL   | UNIT        | TOTAL      | TOTALS         |
| 10200                       | Louvers & vents                     |                 |              | 32.0  | ea   | 2      | 64    | 5315.47   | 100      | 3200.00   | 0        | 0.00    | 0           | 0.00       | \$8,515.47     |
| 10300                       | Projector screens                   |                 |              | 3.0   | ea   | 10     | 30    | 2491.62   | 9000     | 27000.00  | 0        | 0.00    | 0           | 0.00       | \$29,491.62    |
| 10400                       | Interior Signage                    |                 |              | 120.0 | ea   | 2      | 240   | 19932.99  | 140      | 16800.00  | 0        | 0.00    | 0           | 0.00       | \$36,732.99    |
| 10400                       | Exterior Signage                    |                 |              | 1.0   | ea   | 10     | 10    | 830.54    | 0        | 0.00      | 0        | 0.00    | 10000       | 10000.00   | \$10,830.54    |
| 10520                       | Fire extinguishers                  |                 |              | 28.0  | ea   | 2      | 56    | 4651.03   | 225      | 6300.00   | 0        | 0.00    | 0           | 0.00       | \$10,951.03    |
| 10520                       | Knox box                            |                 |              | 1.0   | ea   | 2      | 2     | 166.11    | 520      | 520.00    | 0        | 0.00    | 0           | 0.00       | \$686.11       |
| 10651                       | Operable folding wall               |                 |              | 2.0   | ea   | 20     | 40    | 3322.17   | 35000    | 70000.00  | 0        | 0.00    | 0           | 0.00       | \$73,322.17    |
| 10800                       | Toilet & bath accessories           |                 |              | 261.0 | pcs  | 0.45   | 117   | 9754.71   | 200      | 52200.00  | 0        | 0.00    | 0           | 0.00       | \$61,954.71    |
| DIVISION 10. TOTAL          |                                     |                 |              |       |      |        | 559   | 46464.64  |          | 176020.00 |          | 0.00    |             | 10000.00   | \$232,484.64   |
| DIVISION 12000. FURNISHINGS |                                     |                 |              |       |      |        |       |           |          |           |          |         |             |            |                |
| CODE                        | DESCRIPTION                         | COMPOSITE RATE: | \$8.00 / HR  | QUAN. | UNIT | UNIT   | HRS   | TOTAL     | UNIT     | TOTAL     | UNIT     | TOTAL   | UNIT        | TOTAL      | TOTALS         |
| 12400                       | Appliances - EXCLUDED               |                 |              | 0.0   | job  | 0      | 0     | 0.00      | 0        | 0.00      | 0        | 0.00    | 0           | 0.00       | \$0.00         |
| 12400                       | Mecho shades allowance - Commercial |                 |              | 1.0   | job  | 20     | 20    | 1661.08   | 0        | 0.00      | 0        | 0.00    | 154945      | 154945.00  | \$156,606.08   |
| 12400                       | Glass wall systems - ALLOWANCE      |                 |              | 1.0   | job  | 60     | 60    | 4983.25   | 0        | 0.00      | 0        | 0.00    | 650000      | 650000.00  | \$654,983.25   |
| 12400                       | Embed floor closer for KI           |                 |              | 0.0   | ea   | 2      | 0     | 0.00      | 50       | 0.00      | 0        | 0.00    | 0           | 0.00       | \$0.00         |
| 12400                       | Stock KI walls                      |                 |              | 6.0   | ea   | 50     | 300   | 24916.24  | 0        | 0.00      | 750      | 4500.00 | 0           | 0.00       | \$29,416.24    |
| DIVISION 04. TOTAL          |                                     |                 |              |       |      |        | 380   | 31560.58  |          | 0.00      |          | 4500.00 |             | 804945.00  | \$841,005.58   |



| DIVISION 14000, CONVEYING SYSTEMS |                                     |              |      |       |     |          |          |          |       |             |            |                |
|-----------------------------------|-------------------------------------|--------------|------|-------|-----|----------|----------|----------|-------|-------------|------------|----------------|
| COMPOSITE RATE:                   |                                     |              |      |       |     |          |          |          |       |             |            |                |
| CODE                              | DESCRIPTION                         | \$83.05 / HR |      | LABOR |     | MATERIAL |          | EQUIPMNT |       | SUB / OTHER |            | TOTALS         |
|                                   |                                     | QUAN.        | UNIT | UNIT  | HRS | UNIT     | TOTAL    | UNIT     | TOTAL | UNIT        | TOTAL      |                |
| 14200                             | Elevators - passenger w/ glass back | 2.0          | ea   | 40    | 80  | 15000    | 6644.33  | 0        | 0.00  | 215000      | 430000.00  | \$466,644.33   |
| 14200                             | Elevators - passenger (basement)    | 1.0          | job  | 40    | 40  | 0        | 3322.17  | 0        | 0.00  | 75000       | 75000.00   | \$78,322.17    |
| 14600                             | Elevator hoist way beam             | 3.0          | ea   | 12    | 36  | 500      | 2989.95  | 0        | 0.00  | 0           | 0.00       | \$4,489.95     |
| 14600                             | Elevator work platforms             | 3.0          | ea   | 24    | 72  | 1500     | 5979.90  | 0        | 0.00  | 0           | 0.00       | \$10,479.90    |
| 14600                             | Elevator temporary guard rails      | 16.0         | ea   | 3     | 48  | 300      | 3986.60  | 0        | 0.00  | 0           | 0.00       | \$8,786.60     |
| 14600                             | Pit ladder                          | 2.0          | ea   | 2     | 4   | 750      | 332.22   | 0        | 0.00  | 0           | 0.00       | \$1,832.22     |
|                                   |                                     | 0.0          |      | 0     | 0   | 0        | 0.00     | 0        | 0.00  | 0           | 0.00       | \$0.00         |
| DIVISION 14, TOTAL                |                                     |              |      |       | 280 |          | 23255.16 |          | 0.00  |             | 505000.00  | \$570,555.16   |
|                                   |                                     |              |      |       |     |          |          |          |       |             |            |                |
| DIVISION 15000, MECHANICAL        |                                     |              |      |       |     |          |          |          |       |             |            |                |
| COMPOSITE RATE:                   |                                     |              |      |       |     |          |          |          |       |             |            |                |
| CODE                              | DESCRIPTION                         | \$83.05 / HR |      | LABOR |     | MATERIAL |          | EQUIPMNT |       | SUB / OTHER |            | TOTALS         |
|                                   |                                     | QUAN.        | UNIT | UNIT  | HRS | UNIT     | TOTAL    | UNIT     | TOTAL | UNIT        | TOTAL      |                |
| 15000                             | Mechanical Design Build Allowance   | 1.0          | job  | 60    | 60  | 0        | 4983.25  | 0        | 0.00  | 3497125     | 3497125.00 | \$3,502,108.25 |
| 15000                             | Control wiring                      | 1.0          | job  | 0     | 0   | 0        | 0.00     | 0        | 0.00  | 100000      | 100000.00  | \$100,000.00   |
| 15000                             | Snow melt                           | 1.0          | job  | 10    | 10  | 0        | 830.54   | 0        | 0.00  | 185000      | 185000.00  | \$185,830.54   |
| 15300                             | Fire protection - Chinook           | 1.0          | job  | 0     | 0   | 0        | 0.00     | 0        | 0.00  | 305500      | 305500.00  | \$305,500.00   |
| 15300                             | FM 200 data room                    | 1.0          | job  | 10    | 10  | 0        | 830.54   | 0        | 0.00  | 25000       | 25000.00   | \$25,830.54    |
| 15300                             | Fire tanks and pumps EXCLUDED       | 0.0          | job  | 0     | 0   | 0        | 0.00     | 0        | 0.00  | 0           | 0.00       | \$0.00         |
| DIVISION 15, TOTAL                |                                     |              |      |       | 80  |          | 6644.33  |          | 0.00  |             | 4112625.00 | \$4,119,269.33 |
|                                   |                                     |              |      |       |     |          |          |          |       |             |            |                |
| DIVISION 16000, ELECTRICAL        |                                     |              |      |       |     |          |          |          |       |             |            |                |
| COMPOSITE RATE:                   |                                     |              |      |       |     |          |          |          |       |             |            |                |
| CODE                              | DESCRIPTION                         | \$83.05 / HR |      | LABOR |     | MATERIAL |          | EQUIPMNT |       | SUB / OTHER |            | TOTALS         |
|                                   |                                     | QUAN.        | UNIT | UNIT  | HRS | UNIT     | TOTAL    | UNIT     | TOTAL | UNIT        | TOTAL      |                |
| 16000                             | Electrical Engineering & management | 1.0          | job  | 100   | 100 | 0        | 8305.41  | 0        | 0.00  | 311024      | 311024.00  | \$319,329.41   |
| 16000                             | MDP/panels/buse duct/feeders        | 1.0          | job  | 0     | 0   | 0        | 0.00     | 0        | 0.00  | 350000      | 350000.00  | \$350,000.00   |
| 16000                             | Power - (outlets) ALLOWANCE         | 1.0          | job  | 0     | 0   | 0        | 0.00     | 0        | 0.00  | 367200      | 367200.00  | \$367,200.00   |
| 16000                             | Lighting rough in                   | 1.0          | job  | 0     | 0   | 0        | 0.00     | 0        | 0.00  | 275000      | 275000.00  | \$275,000.00   |
| 16000                             | Light fixtures ALLOWANCE            | 1.0          | job  | 0     | 0   | 0        | 0.00     | 0        | 0.00  | 750000      | 750000.00  | \$750,000.00   |
| 16000                             | Data ALLOWANCE                      | 1.0          | job  | 0     | 0   | 0        | 0.00     | 0        | 0.00  | 250000      | 250000.00  | \$250,000.00   |
| 16000                             | Fire alarm / security               | 1.0          | job  | 0     | 0   | 0        | 0.00     | 0        | 0.00  | 397400      | 397400.00  | \$397,400.00   |
| 16000                             | Video conference -ALLOWANCE         | 1.0          | job  | 0     | 0   | 0        | 0.00     | 0        | 0.00  | 45000       | 45000.00   | \$45,000.00    |
| 16000                             | Generator                           | 1.0          | job  | 0     | 0   | 0        | 0.00     | 0        | 0.00  | 146000      | 146000.00  | \$146,000.00   |
| 16000                             | Parking garage - ALLOWANCE          | 1.0          | job  | 0     | 0   | 0        | 0.00     | 0        | 0.00  | 34500       | 34500.00   | \$34,500.00    |
| 16000                             | Lighting control                    | 1.0          | job  | 0     | 0   | 0        | 0.00     | 0        | 0.00  | 120000      | 120000.00  | \$120,000.00   |
| DIVISION 16, TOTAL                |                                     |              |      |       | 100 |          | 8305.41  |          | 0.00  |             | 3046124.00 | \$3,054,429.41 |
| :                                 | END                                 |              |      |       |     |          |          |          |       |             |            |                |

# **Appendix B**

## ESTIMATE SUMMARY

Items highlighted in red text require further discussion and analysis

| CODE  | DESCRIPTION                                                        |  | TOTALS          |  |                     |                                                  |  |  |  |
|-------|--------------------------------------------------------------------|--|-----------------|--|---------------------|--------------------------------------------------|--|--|--|
|       | <b>DIRECT COSTS</b>                                                |  |                 |  |                     |                                                  |  |  |  |
| 01000 | GENERAL REQUIREMENTS                                               |  | \$ 3,766,738.12 |  |                     |                                                  |  |  |  |
| 02000 | SITEWORK                                                           |  | \$ 3,877,285.41 |  |                     |                                                  |  |  |  |
| 03000 | CONCRETE                                                           |  | \$ 1,380,209.51 |  |                     |                                                  |  |  |  |
| 04000 | MASONRY (NOT USED)                                                 |  | \$ -            |  |                     |                                                  |  |  |  |
| 05000 | METALS                                                             |  | \$ 2,211,553.59 |  |                     |                                                  |  |  |  |
| 06000 | WOOD AND PLASTIC                                                   |  | \$ 351,180.95   |  |                     |                                                  |  |  |  |
| 07000 | THERMAL AND MOISTURE                                               |  | \$ 1,657,400.22 |  |                     |                                                  |  |  |  |
| 08000 | DOORS AND WINDOWS                                                  |  | \$ 2,468,250.79 |  |                     |                                                  |  |  |  |
| 09000 | FINISHES                                                           |  | \$ 2,913,116.64 |  |                     |                                                  |  |  |  |
| 10000 | SPECIALTIES                                                        |  | \$ 232,484.64   |  |                     |                                                  |  |  |  |
| 11000 | EQUIPMENT (NOT USED)                                               |  | \$ -            |  |                     |                                                  |  |  |  |
| 12000 | FURNISHINGS                                                        |  | \$ 29,416.24    |  |                     |                                                  |  |  |  |
| 13000 | SPECIAL CONSTRUCTION (NOT USED)                                    |  | \$ -            |  |                     |                                                  |  |  |  |
| 14000 | CONVEYING SYSTEMS                                                  |  | \$ 570,555.16   |  |                     |                                                  |  |  |  |
| 15000 | MECHANICAL                                                         |  | \$ 4,119,269.33 |  |                     |                                                  |  |  |  |
| 16000 | ELECTRICAL                                                         |  | \$ 3,054,429.41 |  |                     |                                                  |  |  |  |
|       | SUBTOTAL, DIRECT COST                                              |  |                 |  | <b>\$26,631,890</b> |                                                  |  |  |  |
|       | <b>MARKUPS</b>                                                     |  |                 |  |                     |                                                  |  |  |  |
|       | PROFIT / MARKUP (4%)                                               |  | \$ 1,131,855.00 |  |                     |                                                  |  |  |  |
|       | GENERAL OVERHEAD MARKUP (4%)                                       |  | \$ 1,131,855.00 |  |                     |                                                  |  |  |  |
|       | SUBTOTAL, MARKUPS                                                  |  |                 |  | \$ 2,263,710        |                                                  |  |  |  |
|       |                                                                    |  |                 |  | <b>\$28,895,600</b> | <b>\$444.55 PER SF PROJECT (65,000 SF TOTAL)</b> |  |  |  |
|       | <b>FEES &amp; PREMIUMS</b>                                         |  |                 |  |                     |                                                  |  |  |  |
| 00610 | LIABILITY INSURANCE                                                |  | \$ 27,426.19    |  |                     |                                                  |  |  |  |
| 00610 | UMBRELLA PREMIUM                                                   |  | \$ -            |  |                     |                                                  |  |  |  |
| 00620 | DEPARTMENT OF LABOR FEE                                            |  | \$ 5,000.00     |  |                     |                                                  |  |  |  |
| 00620 | BUILDERS ALL-RISK INSURANCE                                        |  | \$ 63,570.32    |  |                     |                                                  |  |  |  |
| 00630 | MOA BUILDING PERMIT / PLAN REVIEW / FIRE REVIEW                    |  | \$ 349,676.72   |  |                     |                                                  |  |  |  |
| 00650 | AWWU                                                               |  | \$ 15,000.00    |  |                     |                                                  |  |  |  |
| 00650 | PARKING RENTAL                                                     |  | \$ 20,000.00    |  |                     |                                                  |  |  |  |
| 00650 | ROAD CLOSURE & TRAFFIC PERMITS                                     |  | \$ 100,000.00   |  |                     |                                                  |  |  |  |
| 00650 | ENSTAR                                                             |  | \$ 5,000.00     |  |                     |                                                  |  |  |  |
| 00650 | ML&P FEES                                                          |  | \$ 40,000.00    |  |                     |                                                  |  |  |  |
|       | SUBTOTAL, FEES & PREMIUMS                                          |  |                 |  | <b>\$625,673</b>    |                                                  |  |  |  |
|       | <b>BOND</b>                                                        |  |                 |  |                     |                                                  |  |  |  |
|       | <b>PERFORMANCE &amp; PAYMENT BOND, IF REQUIRED</b>                 |  | \$ 229,834.00   |  |                     |                                                  |  |  |  |
|       | SUBTOTAL, BOND PREMIUMS                                            |  |                 |  | <b>\$229,834</b>    |                                                  |  |  |  |
|       | <b>TOTAL, ESTIMATED CONSTRUCTION COST - CRITERION [08-27-2013]</b> |  |                 |  | <b>\$29,751,107</b> |                                                  |  |  |  |

|       |                                           |       |      |    |           |                                          |  |        |
|-------|-------------------------------------------|-------|------|----|-----------|------------------------------------------|--|--------|
| 01300 | JOB ADMINISTRATION                        |       |      | \$ | 3,766,738 |                                          |  |        |
| 01310 | PROJECT DESIGN & ENGINEERING              | 1.0   | Job  | \$ | 1,306,644 | LS                                       |  | 34.69% |
| 01310 | EXPLORATORY & ASBUILT WORK                | 1.0   | Job  | \$ | 22,000    | LS                                       |  | 0.58%  |
| 01310 | PROJECT MANAGER                           | 13.0  | Mo   | \$ | 69,982    | \$5,383.25 per MO Project Manger         |  | 1.86%  |
| 01320 | PROJECT SUPERVISION                       | 55.3  | Wks  | \$ | 229,437   | \$4,148.95 per WK Field Supervision      |  | 6.09%  |
| 01325 | SAFETY PROGRAM MANAGER                    | 13.0  | Mo   | \$ | 34,551    | \$2,657.73 per WK Safety Program         |  | 0.92%  |
| 01330 | PROJECT ENGINEER / SUBMITTALS / O&M's     | 13.0  | Mo   | \$ | 28,094    | \$2,161.08 per MO Submittals             |  | 0.75%  |
| 01340 | PROJECT COORDINATOR                       | 13.0  | Mo   | \$ | 10,797    | \$830.54 per MO Coordinating             |  | 0.29%  |
| 01350 | EXPEDITING / PURCHASING                   | 13.0  | Mo   | \$ | 43,188    | \$3,322.17 per MO Expediting             |  | 1.15%  |
|       |                                           |       |      |    |           |                                          |  |        |
| 1400  | Q.C. / FIELD ENG'R.                       |       |      |    |           |                                          |  |        |
| 01420 | CONSTRUCTION STAKING & AS-BUILT PLOT PLAN | 1.0   | Job  | \$ | 8,000     | LS                                       |  | 0.21%  |
| 01430 | TESTING & SPECIAL INSPECTIONS             | 1.0   | Job  | \$ | 80,000    | LS                                       |  | 2.12%  |
|       |                                           |       |      |    |           |                                          |  |        |
| 1500  | TEMPORARY FACILITIES                      |       |      |    |           |                                          |  |        |
| 01501 | FIELD OFFICE                              | 13.0  | Mo   | \$ | 34,638    | \$2,664.43 per MO Field Office           |  | 0.92%  |
| 01501 | TEMP CREW PARKING - USE GARAGE            | 0.0   | Mo   | \$ | -         | n/a                                      |  | 0.00%  |
| 01502 | PROJECT SIGNS                             | 1.0   | Ea   | \$ | 1,831     | \$1,830.54 per EA Project Sign           |  | 0.05%  |
| 01503 | STORAGE CONTAINERS                        | 2.0   | Ea   | \$ | 3,000     | \$1,500.00 per EA Container              |  | 0.08%  |
| 01503 | STORAGE AREA / SECURITY FENCE             | 600.0 | Lf   | \$ | 7,292     | \$12.15 per LF Fencing                   |  | 0.19%  |
| 01504 | TEMPORARY TOILETS                         | 13.0  | Mo   | \$ | 13,650    | \$1,050.00 per MO Toilet                 |  | 0.36%  |
| 01505 | TEMP ELECTRIC SERVICE                     | 1.0   | Job  | \$ | 28,305    | LS                                       |  | 0.75%  |
| 01506 | ELECTRICITY                               | 13.0  | Mo   | \$ | 39,000    | \$3,000.00 per MO Electricity            |  | 1.04%  |
| 01507 | TEMPORARY LIGHTS                          | 13.0  | Flrs | \$ | 23,797    | \$1,830.54 per MO Teno Lights            |  | 0.63%  |
| 01508 | TEMPORARY HEAT                            | 8.0   | Mo   | \$ | 154,577   | \$19,322.17 per MO Temp Heat             |  | 4.10%  |
| 01509 | TELEPHONES                                | 13.0  | Mo   | \$ | 4,550     | \$350.00 per MO Phones                   |  | 0.12%  |
| 01510 | TEMP WEATHER PROTECTION                   | 6.0   | Flrs | \$ | 86,291    | \$14,381.77 per FLOOR Weather Protection |  | 2.29%  |
| 01510 | TEMP PEDESTRIAL WALKWAYS                  | 1.0   | Job  | \$ | 12,305    | LS                                       |  | 0.33%  |
| 01511 | SNOW REMOVAL                              | 5.0   | Mo   | \$ | 16,611    | \$3,322.17 per MO Snow Removal           |  | 0.44%  |
| 01512 | CLEANUP PERIODIC                          | 13.0  | Mo   | \$ | 151,159   | \$11,627.58 per MO Periodic Cleanup      |  | 4.01%  |
| 01513 | CLEANUP FINAL, INC. WINDOWS               | 1.0   | Job  | \$ | 24,811    | LS                                       |  | 0.66%  |



|              |                                      |             |           |           |                  |                    |                                  |               |
|--------------|--------------------------------------|-------------|-----------|-----------|------------------|--------------------|----------------------------------|---------------|
| 01514        | SAFETY SUPPLIES                      | 1.0         | Job       | \$        | 8,000            |                    | LS                               | 0.21%         |
| <b>01515</b> | <b>MATERIAL HANDLING</b>             | <b>13.0</b> | <b>Mo</b> | <b>\$</b> | <b>215,941</b>   | <b>\$16,610.83</b> | <b>per MO Material Handling</b>  | <b>5.73%</b>  |
| 01516        | TRASH HAUL, DUMPSTER                 | 13.0        | Mo        | \$        | 49,313           | \$3,793.30         | per MO Trash Handling            | 1.31%         |
|              |                                      |             |           |           |                  |                    |                                  |               |
| <b>1600</b>  | <b>EQUIPMENT</b>                     |             |           |           |                  |                    |                                  |               |
| 01610        | CONSUMABLES                          | 1.0         | Job       | \$        | 18,000           |                    | LS                               | 0.48%         |
| <b>01620</b> | <b>SCAFFOLDING / MAN LIFTS</b>       | <b>12.0</b> | <b>Mo</b> | <b>\$</b> | <b>42,000</b>    | <b>\$3,500.00</b>  | <b>per MO Scaffolding/Lifts</b>  | <b>1.12%</b>  |
| 01630        | JOB TRUCKS (PICKUP, FLATBED)         | 13.0        | Mo        | \$        | 15,600           | \$1,200.00         | per MO Job Truck                 | 0.41%         |
| 01640        | BOOM TRUCK                           | 8.0         | Mo        | \$        | 24,000           | \$3,000.00         | per MO Boom Truck                | 0.64%         |
| 01640        | FORKLIFT                             | 10.0        | Mo        | \$        | 30,000           | \$3,000.00         | per MO Fork Lift                 | 0.80%         |
| <b>01640</b> | <b>AERIAL BOOM LIFT</b>              | <b>12.0</b> | <b>Mo</b> | <b>\$</b> | <b>96,000</b>    | <b>\$8,000.00</b>  | <b>per MO Aerial Boom Lift</b>   | <b>2.55%</b>  |
| 01650        | MISC RENTAL                          | 13.0        | Mo        | \$        | 6,500            | \$500.00           | per MO Misc Maintenance          | 0.17%         |
| 01660        | FUEL & MAINTENANCE                   | 13.0        | Mo        | \$        | 42,791           | \$3,291.62         | per MO Fuel, Oil, Grease         | 1.14%         |
| <b>01670</b> | <b>CRANE SERVICE</b>                 | <b>11.0</b> | <b>Mo</b> | <b>\$</b> | <b>547,919</b>   | <b>\$49,810.83</b> | <b>per MO Tower Crane Rental</b> | <b>14.55%</b> |
| <b>01680</b> | <b>MAN / EQUIPMENT HOIST</b>         | <b>7.0</b>  | <b>Mo</b> | <b>\$</b> | <b>201,521</b>   | <b>\$28,788.66</b> | <b>per MO Hoist</b>              | <b>5.35%</b>  |
|              |                                      |             |           |           |                  |                    |                                  |               |
| <b>1800</b>  | <b>FREIGHT</b>                       |             |           |           |                  |                    |                                  |               |
| 01820        | GENERAL OCEAN FREIGHT-SEA TO JOBSITE | 4.0         | Loads     | \$        | 26,000           | \$6,500.00         | per LOAD Ocean Freight           | 0.69%         |
| 01860        | MOBE / DEMOBE                        | 1.0         | Job       | \$        | 8,644            |                    | LS                               | 0.23%         |
|              |                                      |             |           |           |                  |                    |                                  |               |
|              | <b>GENERAL REQUIREMENTS, TOTAL</b>   |             |           | <b>\$</b> | <b>3,766,738</b> |                    |                                  | 100.00%       |

Anchorage Downtown Office Building  
BCE Review and Validation of Contractor's Budgetary Estimate [08-27-2013]  
**CONFIDENTIAL**

**ESTIMATE DETAIL BY DIVISION**

Items highlighted in red text require further discussion and analysis

|              |  |                                                  |                  |            |                     |                   |                                 |              |   |
|--------------|--|--------------------------------------------------|------------------|------------|---------------------|-------------------|---------------------------------|--------------|---|
|              |  | <b>DIVISION 02000, SITEWORK</b>                  |                  |            | \$ 26,631,890.03    |                   |                                 |              |   |
| <b>02220</b> |  | <b>ADDITIONAL ASBESTOS ABATEMENT - ALLOWANCE</b> | <b>1.00</b>      | <b>Job</b> | <b>\$ 300,000</b>   |                   | <b>LS</b>                       | <b>1.13%</b> |   |
|              |  | Existing LIO (6 levels + roof)                   | 42,000.00        | SF Levels  |                     | \$5.43            | per SF Floor                    |              |   |
|              |  | Existing Anchor Pub (2 levels + roof)            | 13,200.00        | SF Levels  |                     | \$5.43            | per SF Floor                    |              |   |
| <b>02221</b> |  | <b>DEMOLITION SUBCONTRACTOR - AK DEMO</b>        | <b>1.00</b>      | <b>Job</b> | <b>\$ 2,017,727</b> |                   | <b>LS</b>                       | <b>7.58%</b> |   |
|              |  | Existing LIO & Anchor Pub floors and roofs       | 55,200.00        | SF Levels  |                     | \$36.55           | per SF Levels                   |              |   |
| 02221        |  | TEMPORARY SHORING - BUILDING                     | 1.00             | Job        | \$ 53,222           |                   | LS                              | 0.20%        |   |
| 02221        |  | TEMPORARY SHORING - GARAGE                       | 1.00             | Job        | \$ 61,527           |                   | LS                              | 0.23%        |   |
| 02221        |  | ADDITIONAL DEMOLITION                            | 6.00             | Firs       | \$ 52,832           | \$8,805.42        | per EA Floor                    | 0.20%        | ? |
| 02221        |  | HAUL OFF MISC DEMO DEBRIS                        | 20.00            | Lds        | \$ 26,644           | \$1,332.22        | per EA Haul Load                | 0.10%        |   |
| 02221        |  | REMOVE FLOOR ADHESIVES                           | 61,000.00        | Sf         | \$ 41,047           | \$0.67            | per SF Floor                    | 0.15%        |   |
| 02300        |  | TRAFFIC CONTROL PLAN                             | 1.00             | Job        | \$ 36,305           |                   | LS                              | 0.14%        | ? |
| 02300        |  | TRAFFIC CONTROL PLAN - FLAGGER                   | 8.00             | Mo         | \$ 106,309          | \$13,288.66       | per EA Month                    | 0.40%        | ? |
| <b>02300</b> |  | <b>SITE &amp; UTILITY SUBCONTRACTOR - BCX</b>    | <b>1.00</b>      | <b>Job</b> | <b>\$ 362,622</b>   |                   | <b>LS</b>                       | <b>1.36%</b> |   |
| 02316        |  | TRENCHING FOR M & E INTERIOR BLDG                | 500.00           | Lf         | \$ 3,826            | \$7.65            | per LF Trench                   | 0.01%        |   |
| 02370        |  | SWPPP MANAGEMENT / STREET SWEEPING               | 7.00             | Mo         | \$ 45,383           | \$6,483.25        | per EA Month                    | 0.17%        |   |
| <b>02455</b> |  | <b>H PILING &amp; LAGGING (BASEMENT SHORING)</b> | <b>120.00</b>    | <b>Lf</b>  | <b>\$ 571,933</b>   | <b>\$4,766.11</b> | <b>per LF Shoring</b>           | <b>2.15%</b> |   |
| 02740        |  | ASPHALT PAVEMENT @ ALLEY                         | 4,000.00         | Sf         | \$ 20,000           | \$5.00            | per SF Alley Pavement           | 0.08%        |   |
| 02740        |  | ASPHALT PAVEMENT @ ROADS                         | 4,000.00         | Sf         | \$ 20,000           | \$5.00            | per SF Road Pavement            | 0.08%        |   |
| 02740        |  | ASPHALT SEAL COAT PARKING GARAGE                 | 40,300.00        | Sf         | \$ 20,150           | \$0.50            | per SF Seal Coat                | 0.08%        |   |
| 02760        |  | PAINT MARKINGS - GARAGE                          | 120.00           | Ea         | \$ 4,200            | \$35.00           | per EA Car Parking Stall        | 0.02%        |   |
| 02770        |  | CURB & GUTTER PATCHES                            | 120.00           | Lf         | \$ 4,800            | \$40.00           | per LF Curb & Gutter            | 0.02%        |   |
| 02775        |  | SIDEWALKS & PADS                                 | 3,800.00         | Sf         | \$ 34,490           | \$9.08            | per SF Concrete                 | 0.13%        |   |
| 02775        |  | RAMP - GARAGE                                    | 4,000.00         | Sf         | \$ 44,305           | \$11.08           | per SF Garage Ramp Rehab        | 0.17%        |   |
| 02820        |  | FENCES & GATE - DUMPSTER ENCLOSURE               | 36.00            | Lf         | \$ 7,310            | \$203.05          | per LF Fencing                  | 0.03%        |   |
| 02820        |  | GATES @ GARAGE RAMP                              | 1.00             | Job        | \$ 28,322           |                   | LS                              | 0.11%        |   |
| 02900        |  | LANDSCAPE PLANTING                               | 1.00             | Job        | \$ 5,000            |                   | LS                              | 0.02%        |   |
| 02900        |  | LANDSCAPE FURNISHINGS (BIKE RACK, BENCHES)       | 8.00             | Ea         | \$ 9,329            | \$1,166.11        | per EA Item                     | 0.04%        |   |
|              |  |                                                  |                  |            |                     |                   |                                 |              |   |
|              |  | <b>DIVISION 02, TOTAL</b>                        |                  |            | \$ 3,877,285        | \$59.65           | Direct Cost per SF Project Area | 14.56%       |   |
|              |  |                                                  |                  |            |                     |                   |                                 |              |   |
|              |  | <b>DIVISION 03000, CONCRETE</b>                  |                  |            |                     |                   |                                 |              |   |
| <b>00310</b> |  | <b>FORMWORK</b>                                  | <b>23,000.00</b> | <b>sf</b>  | <b>\$ 306,025</b>   | <b>\$13.31</b>    | <b>per SFA Forms</b>            | <b>1.15%</b> |   |
| 03200        |  | REINFORCING - PURCHASE                           | 190,000.00       | lb         | \$ 142,500          | \$0.75            | per LB Reinforcing, Purchase    | 0.54%        |   |
| 03200        |  | REINFORCING PLACE REBARR                         | 100.00           | ton        | \$ 90,000           | \$900.00          | per TON Rebar, Place            | 0.34%        |   |
| 03200        |  | REINFORCING PLACE WWF                            | 24,572.00        | sf         | \$ 14,931           | \$0.61            | per SF Wire Mesh, Place         | 0.06%        |   |
| 03300        |  | PLACE FOOTING, WALLS, GRADE BEAMS                | 582.00           | cy         | \$ 117,733          | \$202.29          | per CY Concrete, Place          | 0.44%        |   |

CONFIDENTIAL

Items highlighted in red text require further discussion and analysis

|              |  |                                      |                  |            |           |                |                   |                                 |              |   |
|--------------|--|--------------------------------------|------------------|------------|-----------|----------------|-------------------|---------------------------------|--------------|---|
| 03300        |  | PLACE CONCRETE BALLAST SOG           | 580.00           | cy         | \$        | 117,329        | \$202.29          | per CY Concrete, Place          | 0.44%        |   |
| 03300        |  | PLACE CONCRETE ON GRADE/DECK/INFILLS | 362.00           | cy         | \$        | 84,366         | \$233.05          | per CY Concrete, Place          | 0.32%        |   |
| 03300        |  | PLACE & FINISH STAIRS & LANDINGS     | 30.00            | cy         | \$        | 23,675         | \$789.16          | per CY Concrete, Place          | 0.09%        |   |
| 03300        |  | PLACE HOUSEKEEPING PADS              | 30.00            | cy         | \$        | 11,675         | \$389.16          | per CY Concrete, Place          | 0.04%        |   |
| 03300        |  | EDGE OF DECK INFILL                  | 30,000.00        | sf         | \$        | 36,916         | \$1.23            | per SF Deck Edge (?)            | 0.14%        |   |
| 03300        |  | PLACE MISC. CONC                     | 50.00            | cy         | \$        | 18,708         | \$374.16          | per CY Concrete, Place          | 0.07%        |   |
| 03300        |  | GARAGE - UPGRADES                    | 1.00             | Job        | \$        | 196,108        |                   | LS                              | 0.74%        | ? |
| 03350        |  | FINISH CONCRETE SLABS                | 24,572.00        | sf         | \$        | 36,858         | \$1.50            | per SF Concrete Finishes        | 0.14%        |   |
| 03390        |  | CURING / SEALING                     | 24,572.00        | sf         | \$        | 3,269          | \$0.13            | per SF Curing                   | 0.01%        |   |
| 03600        |  | GROUT COLUMN BASES                   | 20.00            | ea         | \$        | 2,661          | \$133.05          | per EA Grout                    | 0.01%        |   |
| 03151        |  | SAWCUT CONTROL JOINTS                | 1,550.00         | lf         | \$        | 5,281          | \$3.41            | per LF Sawcut                   | 0.02%        |   |
| 03050        |  | EPOXY BOLTS                          | 1.00             | Job        | \$        | 139,581        |                   | LS                              | 0.52%        | ? |
| 03050        |  | EMBEDDED ITEMS                       | 1.00             | Job        | \$        | 24,611         |                   | LS                              | 0.09%        |   |
| 03050        |  | ANCHOR BOLTS & TEMPLATES             | 120.00           | ea         | \$        | 7,983          | \$66.53           | per EA Set                      | 0.03%        |   |
|              |  |                                      |                  |            |           |                |                   |                                 |              |   |
|              |  | <b>DIVISION 03, TOTAL</b>            |                  |            | \$        | 1,380,210      | \$21.23           | Direct Cost per SF Project Area | 5.18%        |   |
|              |  |                                      |                  |            |           |                |                   |                                 |              |   |
|              |  | <b>DIVISION 05000, METALS</b>        |                  |            |           |                |                   |                                 |              |   |
| 05090        |  | WELDING ROD, GAS, BOLTS, SUPPLIES    | 1.00             | Job        | \$        | 2,500          |                   | LS                              | 0.01%        |   |
| <b>05100</b> |  | <b>STRUCTURAL STEEL FABRICATION</b>  | <b>44,000.00</b> | <b>lbs</b> | <b>\$</b> | <b>660,000</b> | <b>\$15.00</b>    | <b>per LB Steel</b>             | <b>2.48%</b> |   |
| <b>05100</b> |  | <b>BUCKLING RESTRAINT BRACES</b>     | <b>104.00</b>    | <b>ea</b>  | <b>\$</b> | <b>329,101</b> | <b>\$3,164.43</b> | <b>per EA Brace</b>             | <b>1.24%</b> |   |
| 05100        |  | STAIRWELLS                           | 1.00             | ea         | \$        | 35,000         |                   | LS                              | 0.13%        |   |
| 05100        |  | STRUCTURAL STEEL ERECTION            | 27,572.00        | sf         | \$        | 248,148        | \$9.00            | per SF Deck Area                | 0.93%        |   |
| 05100        |  | STRUCTURAL STEEL DECKING PURCHASE    | 27,572.00        | sf         | \$        | 82,716         | \$3.00            | per SF Deck, Purchase           | 0.31%        |   |
| <b>05100</b> |  | <b>STRUCTURAL STEEL UPGRADES</b>     | <b>1.00</b>      | <b>Job</b> | <b>\$</b> | <b>282,719</b> |                   | <b>LS</b>                       | <b>1.06%</b> |   |
| 05100        |  | SHIP STRUCTURAL STEEL                | 22.00            | lds        | \$        | 143,000        | \$6,500.00        | per EA Haul Load                | 0.54%        |   |
| 05200        |  | STEEL ROOF JOISTS                    | 5,600.00         | sf         | \$        | 33,600         | \$6.00            | per SF Roof                     | 0.13%        |   |
| 05200        |  | SHIP ROOF JOIST & DECK               | 5.00             | lds        | \$        | 39,000         | \$7,800.00        | per EA Haul Load                | 0.15%        |   |
| <b>05400</b> |  | <b>COLD-FORMED METAL FRAMING</b>     | <b>21,800.00</b> | <b>lf</b>  | <b>\$</b> | <b>278,643</b> | <b>\$12.78</b>    | <b>per LF Metal Framing</b>     | <b>1.05%</b> |   |
| 05500        |  | WELDED REBAR @ POUR STOP             | 700.00           | ea         | \$        | 18,034         | \$25.76           | per EA Pour Stop                | 0.07%        |   |
| 05500        |  | ANGLES OPENING THROUGH DECK          | 1.00             | Job        | \$        | 8,483          |                   | LS                              | 0.03%        |   |
| 05500        |  | ANGLES AT ELEVATOR PITS              | 3.00             | ea         | \$        | 1,897          | \$632.22          | per EA Angles                   | 0.01%        |   |
| 05500        |  | MISC. FABRICATED METALS              | 1.00             | Job        | \$        | 9,153          |                   | LS                              | 0.03%        |   |
| 05500        |  | HANDRAILS                            | 600.00           | lf         | \$        | 22,983         | \$38.31           | per LF Railings                 | 0.09%        |   |
| 05500        |  | TEMPORARY GUARD RAILS                | 2,400.00         | lf         | \$        | 16,577         | \$6.91            | per LF Temp Guard Rails         | 0.06%        |   |
|              |  |                                      |                  |            |           |                |                   |                                 |              |   |
|              |  | <b>DIVISION 05, TOTAL</b>            |                  |            | \$        | 2,211,554      | \$34.02           | Direct Cost per SF Project Area | 8.30%        |   |

Anchorage Downtown Office Building  
BCE Review and Validation of Contractor's Budgetary Estimate [08-27-2013]  
**CONFIDENTIAL**

**ESTIMATE DETAIL BY DIVISION**

Items highlighted in red text require further discussion and analysis

|              |  |                                                    |                  |            |           |                |                |                                 |              |
|--------------|--|----------------------------------------------------|------------------|------------|-----------|----------------|----------------|---------------------------------|--------------|
|              |  |                                                    |                  |            |           |                |                |                                 |              |
|              |  | <b><u>DIVISION 06000, WOOD AND PLASTIC</u></b>     |                  |            |           |                |                |                                 |              |
| 06100        |  | CURBS CANTS BLOCKING                               | 4,000.00         | bf         | \$        | 25,289         | \$6.32         | per BF Cant                     | 0.09%        |
| 06160        |  | SHEATHING - DATA BOARDS                            | 280.00           | sf         | \$        | 861            | \$3.08         | per SF Sheathing                | 0.00%        |
| 06160        |  | SHEATHING -PARAPETS                                | 1,800.00         | bf         | \$        | 5,897          | \$3.28         | per BF? Sheathing               | 0.02%        |
| 06160        |  | SHEATHING                                          | 1,700.00         | sf         | \$        | 5,910          | \$3.48         | per SF Sheathing                | 0.02%        |
| 06200        |  | MODULAR ART WALL                                   | 0.00             | ea         | \$        | -              |                | (not included)                  | 0.00%        |
| 06200        |  | CUSTOM FLOOR BASE                                  | 3,000.00         | lf         | \$        | 117,207        | \$39.07        | per LF Floor Base               | 0.44% ?      |
| 06410        |  | CUSTOM CASEWORK - SECURITY DESK                    | 1.00             | Job        | \$        | 21,661         |                | LS                              | 0.08%        |
| 06410        |  | CUSTOM CASEWORK - ALLOWANCE                        | 1.00             | Job        | \$        | 137,458        |                | LS                              | 0.52% ?      |
| 06410        |  | SOLID SURFACE @ RESTROOMS                          | 120.00           | lf         | \$        | 30,384         | \$253.20       | per LF Countertops, etc.        | 0.11%        |
| 06600        |  | FRP PANELS - JANITOR CLOSETS                       | 900.00           | sf         | \$        | 6,514          | \$7.24         | per SF FRP                      | 0.02%        |
|              |  |                                                    |                  |            |           |                |                |                                 |              |
|              |  | <b><u>DIVISION 06, TOTAL</u></b>                   |                  |            | \$        | 351,181        | \$5.40         | Direct Cost per SF Project Area | 1.32%        |
|              |  |                                                    |                  |            |           |                |                |                                 |              |
|              |  | <b><u>DIVISION 07000, THERMAL AND MOISTURE</u></b> |                  |            |           |                |                |                                 |              |
| 07110        |  | FOUNDATION MEMBRANE - E/P                          | 0.00             | sf         | \$        | -              |                | n/a                             | 0.00%        |
| 07110        |  | DAMP PROOFING - E/P                                | 0.00             | sf         | \$        | -              |                | n/a                             | 0.00%        |
| 07210        |  | FOUNDATION INSULATION - E/P                        | 0.00             | sf         | \$        | -              |                | n/a                             | 0.00%        |
| 07210        |  | GARAGE RAMP                                        | 4,000.00         | sf         | \$        | 8,892          | \$2.22         | per SF Board Insulation         | 0.03%        |
| 07210        |  | SIDEWALK INSULATION                                | 2,000.00         | sf         | \$        | 4,446          | \$2.22         | per SF Board Insulation         | 0.02%        |
| 07210        |  | BUILDING INSULATION - COR ACOUSTICAL               | 38,500.00        | sf         | \$        | 57,750         | \$1.50         | per SF Corridor Sound Batt      | 0.22%        |
| 07260        |  | BUILDING INSULATION - EXTERIOR WALL                | 32,000.00        | sf         | \$        | 64,000         | \$2.00         | per SF Exterior Wall            | 0.24%        |
| 07260        |  | AIR BARRIERS                                       | 15,100.00        | sf         | \$        | 22,241         | \$1.47         | per SF Wall                     | 0.08%        |
| 07400        |  | COVER UTILITY SOFFIT PANELS                        | 1,280.00         | sf         | \$        | 46,905         | \$36.64        | per SF Soffit                   | 0.18%        |
| <b>07400</b> |  | <b>METAL SIDING PANELS</b>                         | <b>15,100.00</b> | <b>sf</b>  | <b>\$</b> | <b>552,824</b> | <b>\$36.61</b> | <b>per SF Exterior Wall</b>     | <b>2.08%</b> |
| 07400        |  | MECHANICAL ROOM PANELS                             | 3,240.00         | sf         | \$        | 215,819        | \$66.61        | per SF Mech Penthouse Wall      | 0.81%        |
| <b>07500</b> |  | <b>MEMBRANE ROOFING ALLOWANCE - E/P</b>            | <b>1.00</b>      | <b>Job</b> | <b>\$</b> | <b>375,000</b> |                | <b>LS</b>                       | <b>1.41%</b> |
| 07600        |  | FLASHING & SHEET METAL TRIM                        | 4,000.00         | lf         | \$        | 29,967         | \$7.49         | per LF Flashing/Trim            | 0.11%        |
| 07800        |  | FIRE STOPING-SAFING @ PENETRATIONS                 | 400.00           | ea         | \$        | 18,611         | \$46.53        | per EA Firestop                 | 0.07%        |
| 07800        |  | FIRE STOPING-PERIMETER ANGLES                      | 3,690.00         | lf         | \$        | 60,449         | \$16.38        | per LF Perimeter                | 0.23%        |
| 07800        |  | SPRAY FIREPROOFING - BRADSHAW                      | 68,848.00        | sf         | \$        | 189,332        | \$2.75         | per SF Project Area             | 0.71%        |
| 07900        |  | CAULKING & SEALANTS - INTERIORS                    | 1.00             | Job        | \$        | 3,722          |                | LS                              | 0.01%        |
| 07900        |  | CAULKING & SEALANTS - EXTERIORS                    | 1.00             | Job        | \$        | 7,444          |                | LS                              | 0.03%        |
|              |  |                                                    |                  |            |           |                |                |                                 |              |
|              |  | <b><u>DIVISION 07, TOTAL</u></b>                   |                  |            | \$        | 351,181        | \$5.40         | Direct Cost per SF Project Area | 1.32%        |
|              |  |                                                    |                  |            |           |                |                |                                 |              |
|              |  | <b><u>DIVISION 08000, DOORS AND WINDOWS</u></b>    |                  |            |           |                |                |                                 |              |



**CONFIDENTIAL**

Items highlighted in red text require further discussion and analysis

|              |                                                     |                   |            |           |                  |                       |                                 |              |
|--------------|-----------------------------------------------------|-------------------|------------|-----------|------------------|-----------------------|---------------------------------|--------------|
| 08100        | HM FRAMES & DOORS                                   | 95.00             | ea         | \$        | 215,121          | \$2,264.43            | per EA Door incl Hardware       | 0.81%        |
| 08310        | ACCESS DOORS                                        | 20.00             | ea         | \$        | 2,361            | \$118.05              | per EA Access Door              | 0.01%        |
| 08400        | FORMS AND SURFACE GLASS ALLOWANCE                   | 1,500.00          | sf         | \$        | 124,958          | \$83.31               | per SF Allowance ?              | 0.47% ?      |
| 08800        | GLASS & GLAZING                                     | 1.00              | Job        | \$        | 6,658            | \$6,657.73            | LS                              | 0.02%        |
| 08900        | EXTRUDED ALUMINUM SILLS                             | 0.00              | lf         | \$        | -                |                       | not used                        | 0.00%        |
| 08900        | CANOPIES                                            | 1.00              | Job        | \$        | 15,831           | \$15,830.54           | LS                              | 0.06%        |
| <b>08900</b> | <b>GLAZED CURTAIN WALL &amp; ALUMINUM ENTRANCES</b> | <b>1.00</b>       | <b>Job</b> | <b>\$</b> | <b>2,103,322</b> | <b>\$2,103,322.17</b> | <b>LS</b>                       | <b>7.90%</b> |
|              |                                                     |                   |            |           |                  |                       |                                 |              |
|              | <b>DIVISION 08, TOTAL</b>                           |                   |            | \$        | 2,468,251        | \$37.97               | Direct Cost per SF Project Area | 9.27%        |
|              |                                                     |                   |            |           |                  |                       |                                 |              |
|              | <b>DIVISION 09000, FINISHES</b>                     |                   |            |           |                  |                       |                                 |              |
| 09100        | METAL STUDS -FURRING INTERIOR                       | 51,486.00         | lf         | \$        | 188,279          | \$3.66                | per SF Furring                  | 0.71%        |
| <b>09100</b> | <b>METAL STUDS - PARTITION INTERIOR</b>             | <b>111,119.00</b> | <b>lf</b>  | <b>\$</b> | <b>445,242</b>   | <b>\$4.01</b>         | <b>per LF Partitions</b>        | <b>1.67%</b> |
| 09120        | GYP CEILING SUSPENSION SYSTEMS                      | 18,298.00         | sf         | \$        | 130,880          | \$7.15                | per SF Ceiling Suspension       | 0.49% ?      |
| <b>09260</b> | <b>GWB - STOCK &amp; HANG</b>                       | <b>298,830.00</b> | <b>sf</b>  | <b>\$</b> | <b>397,606</b>   | <b>\$1.33</b>         | <b>per SF GWB</b>               | <b>1.49%</b> |
| 09260        | EXTERIOR GYP                                        | 15,100.00         | sf         | \$        | 34,897           | \$2.31                | per SF Exterior Wall            | 0.13%        |
| 09260        | SHAFT WALL                                          | 14,000.00         | sf         | \$        | 102,510          | \$7.32                | per SF Elevator Shaft           | 0.38%        |
| 09260        | TILE BACKER                                         | 2,224.00          | sf         | \$        | 7,175            | \$3.23                | per SF Tile Area                | 0.03%        |
| 09300        | TILE - ALLOWANCE                                    | 1.00              | Job        | \$        | 201,661          | \$201,661.08          | LS                              | 0.76% ?      |
| <b>09510</b> | <b>CEILINGS ALLOWANCE</b>                           | <b>50,000.00</b>  | <b>sf</b>  | <b>\$</b> | <b>260,382</b>   | <b>\$5.21</b>         | <b>per SF Allowance</b>         | <b>0.98%</b> |
| 09640        | FLOOR PREP                                          | 60,000.00         | sf         | \$        | 52,832           | \$0.88                | per SF Floor                    | 0.20%        |
| <b>09680</b> | <b>FLOORING - ALLOWANCE</b>                         | <b>60,000.00</b>  | <b>sf</b>  | <b>\$</b> | <b>409,983</b>   | <b>\$6.83</b>         | <b>per SF Floor</b>             | <b>1.54%</b> |
| 09680        | ENTRY FLOOR SYSTEM                                  | 1.00              | Job        | \$        | 18,322           | \$18,322.17           | LS                              | 0.07%        |
| <b>09900</b> | <b>PAINTING &amp; TAPING</b>                        | <b>1.00</b>       | <b>Job</b> | <b>\$</b> | <b>452,627</b>   | <b>\$452,626.71</b>   | <b>LS</b>                       | <b>1.70%</b> |
| 09900        | PAINTING - GARAGE                                   | 1.00              | Job        | \$        | 66,729           | \$66,729.08           | LS                              | 0.25%        |
| 09950        | WALLCOVERINGS - RESTROOM ALLOWANCE                  | 10,780.00         | sf         | \$        | 86,240           | \$8.00                | per SF Restroom Wall            | 0.32%        |
| 09950        | WALLCOVERINGS FANCY - ALLOWANCE                     | 770.00            | sf         | \$        | 57,750           | \$75.00               | per SF Special Coverings        | 0.22%        |
|              |                                                     |                   |            |           |                  |                       |                                 |              |
|              | <b>DIVISION 09, TOTAL</b>                           |                   |            | \$        | 2,913,117        | \$44.82               | Direct Cost per SF Project Area | 10.94%       |
|              |                                                     |                   |            |           |                  |                       |                                 |              |
|              | <b>DIVISION 10000, SPECIALTIES</b>                  |                   |            |           |                  |                       |                                 |              |
| 10200        | LOUVERS & VENTS                                     | 32.00             | ea         | \$        | 8,515            | \$266.11              | per EA Opening                  | 0.03%        |
| 10300        | PROJECTOR SCREENS                                   | 3.00              | ea         | \$        | 29,492           | \$9,830.54            | per EA Projector                | 0.11%        |
| 10400        | INTERIOR SIGNAGE                                    | 120.00            | ea         | \$        | 36,733           | \$306.11              | per EA Interior Sign            | 0.14%        |
| 10400        | EXTERIOR SIGNAGE                                    | 1.00              | ea         | \$        | 10,831           | \$10,830.54           | LS                              | 0.04%        |
| 10520        | FIRE EXTINGUISHERS                                  | 28.00             | ea         | \$        | 10,951           | \$391.11              | per EA Extinguisher             | 0.04%        |
| 10520        | KNOX BOX                                            | 1.00              | ea         | \$        | 686              | \$686.11              | per EA Knox Box                 | 0.00%        |

# ESTIMATE DETAIL BY DIVISION

CONFIDENTIAL

Items highlighted in red text require further discussion and analysis

|              |  |                                                 |             |            |           |                  |                       |                                 |                 |
|--------------|--|-------------------------------------------------|-------------|------------|-----------|------------------|-----------------------|---------------------------------|-----------------|
| 10651        |  | OPERABLE FOLDING WALL                           | 2.00        | ea         | \$        | 73,322           | \$36,661.09           | per Operable Wall               | 0.28%           |
| 10800        |  | TOILET & BATH ACCESSORIES                       | 261.00      | pcs        | \$        | 61,955           | \$237.37              | per Restroom Accessory          | 0.23%           |
|              |  |                                                 |             |            |           |                  |                       |                                 |                 |
|              |  | <b>DIVISION 10, TOTAL</b>                       |             |            | \$        | 232,485          | \$3.58                | Direct Cost per SF Project Area | 0.87%           |
|              |  |                                                 |             |            |           |                  |                       |                                 |                 |
|              |  | <b><u>DIVISION 12000, FURNISHINGS</u></b>       |             |            |           |                  |                       |                                 |                 |
| 12400        |  | APPLIANCES - EXCLUDED                           | 0.00        | Job        | \$        | -                |                       | (not included)                  | 0.00%           |
| 12400        |  | MECHO SHADES ALLOWANCE - COMMERCIAL             | 1.00        | Job        | \$        | 156,606          | \$156,606.08          | LS                              | 0.59% ?         |
| <b>12400</b> |  | <b>GLASS WALL SYSTEMS - ALLOWANCE</b>           | <b>1.00</b> | <b>Job</b> | <b>\$</b> | <b>654,983</b>   | <b>\$654,983.25</b>   | <b>LS</b>                       | <b>2.46% ??</b> |
| 12400        |  | EMBED FLOOR CLOSER FOR KI                       | 0.00        | ea         | \$        | -                |                       | (not included)                  | 0.00%           |
| 12400        |  | STOCK KI WALLS                                  | 6.00        | ea         | \$        | 29,416           | \$4,902.71            | per EA Stock Wall               | 0.11%           |
|              |  |                                                 |             |            |           |                  |                       |                                 |                 |
|              |  | <b>DIVISION 04, TOTAL</b>                       |             |            | \$        | 841,006          | \$12.94               | Direct Cost per SF Project Area | 3.16%           |
|              |  |                                                 |             |            |           |                  |                       |                                 |                 |
|              |  | <b><u>DIVISION 14000, CONVEYING SYSTEMS</u></b> |             |            |           |                  |                       |                                 |                 |
| <b>14200</b> |  | <b>ELEVATORS - PASSENGER W/ GLASS BACK</b>      | <b>2.00</b> | <b>ea</b>  | <b>\$</b> | <b>466,644</b>   | <b>\$233,322.17</b>   | <b>per EA Elevator</b>          | <b>1.75%</b>    |
| 14200        |  | ELEVATORS - PASSENGER (BASEMENT)                | 1.00        | Job        | \$        | 78,322           | \$78,322.17           | per EA Elevator                 | 0.29%           |
| 14600        |  | ELEVATOR HOIST WAY BEAM                         | 3.00        | ea         | \$        | 4,490            | \$1,496.65            | per EA Hoist Beam               | 0.02%           |
| 14600        |  | ELEVATOR WORK PLATFORMS                         | 3.00        | ea         | \$        | 10,480           | \$3,493.30            | per EA Work Platform            | 0.04%           |
| 14600        |  | ELEVATOR TEMPORARY GUARD RAILS                  | 16.00       | ea         | \$        | 8,787            | \$549.16              | per EA Temp Guard Rail          | 0.03%           |
| 14600        |  | PIT LADDER                                      | 2.00        | ea         | \$        | 1,832            | \$916.11              | per Ladder                      | 0.01%           |
|              |  |                                                 |             |            |           |                  |                       |                                 |                 |
|              |  | <b>DIVISION 14, TOTAL</b>                       |             |            | \$        | 570,555          | \$8.78                | Direct Cost per SF Project Area | 2.14%           |
|              |  |                                                 |             |            |           |                  |                       |                                 |                 |
|              |  | <b><u>DIVISION 15000, MECHANICAL</u></b>        |             |            |           |                  |                       |                                 |                 |
| <b>15000</b> |  | <b>MECHANICAL DESIGN BUILD ALLOWANCE</b>        | <b>1.00</b> | <b>Job</b> | <b>\$</b> | <b>3,502,108</b> | <b>\$3,502,108.25</b> | <b>LS</b>                       | <b>13.15%</b>   |
| 15000        |  | CONTROL WIRING                                  | 1.00        | Job        | \$        | 100,000          | \$100,000.00          | LS                              | 0.38%           |
| 15000        |  | SNOW MELT                                       | 1.00        | Job        | \$        | 185,831          | \$185,830.54          | LS                              | 0.70% ?         |
| <b>15300</b> |  | <b>FIRE PROTECTION - CHINOOK</b>                | <b>1.00</b> | <b>Job</b> | <b>\$</b> | <b>305,500</b>   | <b>\$305,500.00</b>   | <b>LS</b>                       | <b>1.15%</b>    |
| 15300        |  | FM 200 DATA ROOM                                | 1.00        | Job        | \$        | 25,831           | \$25,830.54           | LS                              | 0.10%           |
| 15300        |  | FIRE TANKS AND PUMPS EXCLUDED                   | 0.00        | Job        | \$        | -                |                       | (excluded)                      | 0.00%           |
|              |  |                                                 |             |            |           |                  |                       |                                 |                 |
|              |  | <b>DIVISION 15, TOTAL</b>                       |             |            | \$        | 4,119,269        | \$63.37               | Direct Cost per SF Project Area | 15.47%          |
|              |  |                                                 |             |            |           |                  |                       |                                 |                 |
|              |  | <b><u>DIVISION 16000, ELECTRICAL</u></b>        |             |            |           |                  |                       |                                 |                 |
| <b>16000</b> |  | <b>ELECTRICAL ENGINEERING &amp; MANAGEMENT</b>  | <b>1.00</b> | <b>Job</b> | <b>\$</b> | <b>319,329</b>   | <b>\$319,329.41</b>   | <b>LS</b>                       | <b>1.20%</b>    |
| <b>16000</b> |  | <b>MDP/PANELS/BUSE DUCT/FEEDERS</b>             | <b>1.00</b> | <b>Job</b> | <b>\$</b> | <b>350,000</b>   | <b>\$350,000.00</b>   | <b>LS</b>                       | <b>1.31%</b>    |

## ESTIMATE DETAIL BY DIVISION

Items highlighted in red text require further discussion and analysis

|       |  |                              |      |     |                     |                |                                        |               |
|-------|--|------------------------------|------|-----|---------------------|----------------|----------------------------------------|---------------|
| 16000 |  | POWER - (OUTLETS) ALLOWANCE  | 1.00 | Job | \$ 367,200          | \$367,200.00   | LS                                     | 1.38%         |
| 16000 |  | LIGHTING ROUGH IN            | 1.00 | Job | \$ 275,000          | \$275,000.00   | LS                                     | 1.03%         |
| 16000 |  | LIGHT FIXTURES ALLOWANCE     | 1.00 | Job | \$ 750,000          | \$750,000.00   | LS                                     | 2.82%         |
| 16000 |  | DATA ALLOWANCE               | 1.00 | Job | \$ 250,000          | \$250,000.00   | LS                                     | 0.94%         |
| 16000 |  | FIRE ALARM / SECURITY        | 1.00 | Job | \$ 397,400          | \$397,400.00   | LS                                     | 1.49%         |
| 16000 |  | VIDEO CONFERENCE - ALLOWANCE | 1.00 | Job | \$ 45,000           | \$45,000.00    | LS                                     | 0.17%         |
| 16000 |  | GENERATOR                    | 1.00 | Job | \$ 146,000          | \$146,000.00   | LS                                     | 0.55%         |
| 16000 |  | PARKING GARAGE - ALLOWANCE   | 1.00 | Job | \$ 34,500           | \$34,500.00    | LS                                     | 0.13%         |
| 16000 |  | LIGHTING CONTROL             | 1.00 | Job | \$ 120,000          | \$120,000.00   | LS                                     | 0.45%         |
|       |  |                              |      |     |                     |                |                                        |               |
|       |  | <b>DIVISION 16, TOTAL</b>    |      |     | <b>\$ 3,054,429</b> | <b>\$46.99</b> | <b>Direct Cost per SF Project Area</b> | <b>11.47%</b> |

# **Appendix C**



*Appendix C - Photographs*

*Cost Estimating Review Services for Downtown Development at 716 W 4th Avenue, Anchorage, AK*



*Photo 1: Ariel View #1*



*Photo 2: Ariel View #2*

*Appendix C - Photographs*

*Cost Estimating Review Services for Downtown Development at 716 W 4th Avenue, Anchorage, AK*



*Photo 3: Ariel view #3 Roof and Parking Lot*



*Photo 4: Ariel View #4 Anchor Pub and LIO Roofs*



*Appendix C - Photographs*

*Cost Estimating Review Services for Downtown Development at 716 W 4th Avenue, Anchorage, AK*



*Photo 5: Ariel View #5 LIO Roof*




*Photo 6: North Elevation*

*Appendix C - Photographs*

*Cost Estimating Review Services for Downtown Development at 716 W 4th Avenue, Anchorage, AK*



*Photo 7: North Elevation Close Up*




*Photo 8: Northwest Elevation*

*Appendix C - Photographs*

*Cost Estimating Review Services for Downtown Development at 716 W 4th Avenue, Anchorage, AK*



*Photo 9: West Elevation*



*Photo 10: West Elevation Close up*



*Appendix C - Photographs*

*Cost Estimating Review Services for Downtown Development at 716 W 4th Avenue, Anchorage, AK*



*Photo 11: West Elevation closer up*



*Photo 12: Southwest Corner looking up*

*Appendix C - Photographs*

*Cost Estimating Review Services for Downtown Development at 716 W 4th Avenue, Anchorage, AK*



*Photo 13: South elevation looking up*




*Photo 14: Southwest corner looking up*

*Appendix C - Photographs*

*Cost Estimating Review Services for Downtown Development at 716 W 4th Avenue, Anchorage, AK*



*Photo 15: Northeast Elevation*



*Photo 16: Parking Lot*



*Appendix C - Photographs*

*Cost Estimating Review Services for Downtown Development at 716 W 4th Avenue, Anchorage, AK*



*Photo 17: Parking Ramp*



*Appendix C - Photographs*

*Cost Estimating Review Services for Downtown Development at 716 W 4th Avenue, Anchorage, AK*



*Photo 18: Parking Ramp and West Elevation*



*Photo 19: Parking Garage Entrance*

*Appendix C - Photographs*

*Cost Estimating Review Services for Downtown Development at 716 W 4th Avenue, Anchorage, AK*



*Photo 20: Parking Ramp and Alley*



*Photo 21: Parking Garage Close up*




*Appendix C - Photographs*

*Cost Estimating Review Services for Downtown Development at 716 W 4th Avenue, Anchorage, AK*



*Photo 22: West elevation from G street*




*Photo 23: Fourth Ave looking east*

*Appendix C - Photographs*

*Cost Estimating Review Services for Downtown Development at 716 W 4th Avenue, Anchorage, AK*



*Photo 24: Fourth Ave looking west*



*Photo 25: Looking North Along G Street*



*Appendix C - Photographs*

*Cost Estimating Review Services for Downtown Development at 716 W 4th Avenue, Anchorage, AK*



*Photo 26: Looking South Along G Street*



*Photo 27: Alley view behind LIO*

*Appendix C - Photographs*

*Cost Estimating Review Services for Downtown Development at 716 W 4th Avenue, Anchorage, AK*



*Photo 28: Utilities in Alley behind LIO*



*Photo 29: South Wall of Anchor Pub*



*Appendix C - Photographs*

*Cost Estimating Review Services for Downtown Development at 716 W 4th Avenue, Anchorage, AK*



*Photo 30: South End of Anchor Pub Building*



*Photo 31: Anchor Pub Entrance*

*Appendix C - Photographs*

*Cost Estimating Review Services for Downtown Development at 716 W 4th Avenue, Anchorage, AK*



*Photo 32: LIO Entrance*